

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2582414

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☐ Drill, ☐ Deepen, ☐ Re-enter, ☒ **Recomplete and Operate**

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☒

Refilling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: FRANCIS D. CLARK UNIT B Well Number: 1

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8220

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 14 Twp: 1N Rng: 67W Meridian: 6

Latitude: 40.046853 Longitude: -104.863758

Footage at Surface: 1120 FNL/FSL FSL 990 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4984 13. County: WELD

14. GPS Data:

Date of Measurement: 07/23/2008 PDOP Reading: 3.0 Instrument Operator's Name: CODY MATTSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 105 ft

18. Distance to nearest property line: 150 ft 19. Distance to nearest well permitted/completed in the same formation: 2466 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407	160	SW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010125

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED OIL & GAS LEASE.

25. Distance to Nearest Mineral Lease Line: 990 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	219	175	219	10
1ST	7+7/8	4+1/2	11.6	8,150	200	8,150	7,400
			Stage Tool	809	200	809	200

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments Section II No. 17 operator states "This well was drilled in 1973 so the set backs should have been grandfathered in per the COGCC as it was prior to 04/26/99. The distance is to a barn."

34. Location ID: 317773

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: REGULATORY Date: 4/23/2010 Email: CHERYL.LIGHT@ANADARKO.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 5/27/2010

API NUMBER

05 123 07740 00

Permit Number: _____ Expiration Date: 5/26/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Prior to recomplete, operator must:

- 1) Verify existing cement with a cement bond log.
- 2) If it is not present as follows, provide remedial cement 200' above Niobrara (minimum cement top of 7000'), 200' below Sussex to 200' above Sussex (minimum coverage 4870' to 4370'). Verify remedial cement coverage with cement bond log.
- 3) Submit wellbore diagram with annotations. (WBDs received – static diagram with well table and WBD with depths and cement tops – no casing dimensions – need well table details incorporated into WBD) Verify DV cement at 809' into SC.

Attachment Check List

Att Doc Num	Name	Doc Description
1770318	SURFACE CASING CHECK	LF@2482464 1770318
2582414	APD ORIGINAL	LF@2457881 2582414
2582415	30 DAY NOTICE LETTER	LF@2457882 2582415
2582416	OIL & GAS LEASE	LF@2457883 2582416

Total Attach: 4 Files