

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1698368

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: MATT BARBER Phone: (303)312-8168 Fax: (303)291-0420
Email: MBARBER@BILLBARRETTCORP.COM

7. Well Name: GGU DALEY Well Number: 31B-30-691

8. Unit Name (if appl): GIBSON GULCH Unit Number: COC052447
X

9. Proposed Total Measured Depth: 7629

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 19 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.506442 Longitude: -107.598992

Footage at Surface: 252 FNL/FSL 2018 FEL/FWL FWL

11. Field Name: MAMM CREEK Field Number: 52500

12. Ground Elevation: 5823 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/30/2009 PDOP Reading: 6.0 Instrument Operator's Name: J. KALMON ECLIPSE SURVEY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL
850 FNL 1983 FEL 850 FNL 1983 FEL
Sec: 30 Twp: 6S Rng: 91W Sec: 30 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 221 ft

18. Distance to nearest property line: 252 ft 19. Distance to nearest well permitted/completed in the same formation: 204 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
ILES	ILES	191-65		
WILLIAMS FORK	WMFK	191-9		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED LEASE BOUNDARY MAP.

25. Distance to Nearest Mineral Lease Line: 1784 ft 26. Total Acres in Lease: 528

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: EVAPORATION & BACKFIL

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42	40		40	0
SURF	12+1/4	9+5/8	36	800	250	800	0
1ST	8+3/4	4+1/2	11.6	7,629	610	7,629	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments THIS PROPOSED WELL IS LOCATED AT AN EXISTING LOCATION THAT HAS BEEN RECLAIMED. A NEW LOCATION ASSESSMENT HAS BEEN SUBMITTED FOR THE PROPOSED EXPANSION AT THIS LOCATION UNDER THE PENDING GGU DALEY 14A-19-691 FORM 2A. (DOC #400055201) PROD'N CSG TOC 500' or more ABOVE TOP OF GAS.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: MATT BARBER

Title: PERMITTING Date: 4/15/2010 Email: MBARBER@BILLBARRETT.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/4/2010

API NUMBER

05 045 19583 00

Permit Number: _____ Expiration Date: 6/3/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLY WITH NOTIFICATION REQUIREMENTS OF THE MOST CURRENT VERSION OF THE NORTHWEST COLORADO NOTIFICATION POLICY.

24-HOUR NOTICE TO MOVE ON LOCATION REQUIRED. E-MAIL Mike.Longworth@state.co.us

ALSO E-MAIL Shaun.Kellerby@state.co.us

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 210 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1698368	APD ORIGINAL	LF@2461009 1698368
1698370	WELL LOCATION PLAT	LF@2461047 1698370
1698371	TOPO MAP	LF@2461115 1698371
1698373	MINERAL LEASE MAP	LF@2461116 1698373
1698375	DRILLING PLAN	LF@2461010 1698375
1698378	DEVIATED DRILLING PLAN	LF@2461011 1698378
1698379	SURFACE AGRMT/SURETY	LF@2461012 1698379
2553249	MINERAL LEASE MAP	LF@2461117 2553249

Total Attach: 8 Files