

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

1760667

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: NICK G. CURRAN Phone: (720)876-5288 Fax: (720)876-6288
Email: NICK.CURRAN@ENCANA.COM

7. Well Name: DIER Well Number: 8-6-8

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8611

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 8 Twp: 2N Rng: 67W Meridian: 6

Latitude: 40.151270 Longitude: -104.907000

Footage at Surface: 2049 FNL/FSL FSL 675 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4949 13. County: WELD

14. GPS Data:

Date of Measurement: 03/17/2010 PDOP Reading: 1.1 Instrument Operator's Name: CRAIG BURKE

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1300 FSL 50 FEL 50 FEL 50 FEL 50
Bottom Hole: FNL/FSL 1300 FSL 50 FEL 50 FEL 50
Sec: 8 Twp: 2N Rng: 67W Sec: 8 Twp: 2N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 292 ft

18. Distance to nearest property line: 175 ft 19. Distance to nearest well permitted/completed in the same formation: 931 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20090011

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2N-R67W SEC. 8: SE & SEC. 18: SE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	800	350	800	0
1ST	7+7/8	4+1/2	11.6	8,611	320	8,611	7,384

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED GWA SPACING UNIT: SEC 8: E2SE & SEC 9: W2SW

34. Location ID: 404815

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: NICK G. CURRAN

Title: REGULATORY Date: 4/1/2010 Email: NICK.CURRAN@ENCANA.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/9/2010

API NUMBER

05 123 31712 00

Permit Number: _____ Expiration Date: 6/8/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.

3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us

2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.

3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1760667	APD ORIGINAL	LF@2444261 1760667
1760669	WELL LOCATION PLAT	LF@2444262 1760669
1760670	TOPO MAP	LF@2444332 1760670
1760671	LEASE MAP	LF@2444333 1760671
1760672	30 DAY NOTICE LETTER	LF@2444263 1760672
1760673	DEVIATED DRILLING PLAN	LF@2444342 1760673
1760674	PROPOSED SPACING UNIT	LF@2444264 1760674
1770323	SURFACE CASING CHECK	LF@2482469 1770323

Total Attach: 8 Files