

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400057369

Plugging Bond Surety

20010124

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461
Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: BRYANT Well Number: 36-30

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8317

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 30 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.103055 Longitude: -105.041715

Footage at Surface: 284 FNL/FSL FSL 1360 FEL/FWL FEL

11. Field Name: SPINDLE Field Number: 77900

12. Ground Elevation: 4928 13. County: WELD

14. GPS Data:

Date of Measurement: 03/17/2010 PDOP Reading: 2.1 Instrument Operator's Name: TRAVIS KRAICH

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 50 FSL 2500 FWL FWL Bottom Hole: FNL/FSL 50 FSL 2500 FWL FWL
Sec: 30 Twp: 2N Rng: 68W Sec: 30 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 285 ft

18. Distance to nearest property line: 284 ft 19. Distance to nearest well permitted/completed in the same formation: 2021 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-SAND	JSND		160	GWA
NIOBRARA-CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED OIL & GAS LEASE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 80

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	850	595	850	
1ST	7+7/8	4+1/2	11.6	8,317	200	8,317	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED GWA SPACING UNIT NB-CD & JSND: SEC 30-SESW, SWSE; SEC 31-NENW, NWNE Kerr McGee requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 4/29/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David G. Neslin Director of COGCC Date: 6/11/2010

API NUMBER

05 123 31729 00

Permit Number: _____ Expiration Date: 6/10/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
2621458	SURFACE CASING CHECK	LF@2465346 2621458
2621531	EXCEPTION LOC REQUEST	LF@2488849 2621531
400057369	FORM 2 SUBMITTED	LF@2460069 400057369
400057371	WELL LOCATION PLAT	LF@2460070 400057371
400057372	TOPO MAP	LF@2460071 400057372
400057373	OIL & GAS LEASE	LF@2460072 400057373
400057374	SURFACE AGRMT/SURETY	LF@2460073 400057374
400057375	DEVIATED DRILLING PLAN	LF@2460074 400057375
400057376	30 DAY NOTICE LETTER	LF@2460075 400057376
400057377	EXCEPTION LOC WAIVERS	LF@2460076 400057377
400057378	EXCEPTION LOC REQUEST	LF@2460077 400057378
400057379	PROPOSED SPACING UNIT	LF@2460078 400057379
400057380	MULTI-WELL PLAN	LF@2460080 400057380

Total Attach: 13 Files