

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL
OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refilling
Sidetrack

Document Number:
400060983
Plugging Bond Surety
20030009

3. Name of Operator: NOBLE ENERGY INC 4. COGCC Operator Number: 100322
5. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
6. Contact Name: Cheryl Johnson Phone: (303)228-4437 Fax: (303)228-4286
Email: cheryljohnson@nobleenergyinc.com
7. Well Name: Timm PC GK Well Number: 04-12
8. Unit Name (if appl): _____ Unit Number: _____
9. Proposed Total Measured Depth: 7885

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 4 Twp: 11N Rng: 61W Meridian: 6
Latitude: 40.948890 Longitude: -104.217450
Footage at Surface: 1980 FNL/FSL FSL 660 FEL/FWL FWL
11. Field Name: Grover Field Number: 33380
12. Ground Elevation: 5255 13. County: WELD

14. GPS Data:
Date of Measurement: 10/08/2009 PDOP Reading: 2.2 Instrument Operator's Name: Nicole Hay

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**
Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____
Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? Yes No
17. Distance to the nearest building, public road, above ground utility or railroad: 630 ft
18. Distance to nearest property line: 660 ft 19. Distance to nearest well permitted/completed in the same formation: 3060 ft

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	Unspaced	40	NWSW
Dakota	DKTA	Unspaced	40	NWSW
JSand	JSND	Unspaced	40	NWSW
Niobrara	NBRR	Unspaced	40	NWSW

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 T11N R61W: Section 4 W2 less 16.82 acre tract - mineral lease attached

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 305

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
 Method: Land Farming Land Spreading Disposal Facility Other: Closed Loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	500	212	500	
1ST	7+7/8	5+1/2	17	7,885	573	7,885	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments No conductor casing will be used. 1st String TOC = 200 ft above Niobrara. Distances listed as 5280 are over 1 mile.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cheryl Johnson

Title: Regulatory Analyst Date: 5/17/2010 Email: cheryljohnson@nobleenergyinc

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/14/2010

API NUMBER
05 123 31742 00

Permit Number: _____ Expiration Date: 6/13/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME

- 1) Provide 24 hr notice of spud to Bo Brown at 970-392-4124 or e-mail at bo.brown@state.co.us.
- 2) Note surface casing setting depth change from 500' to 1170'. Increase cement coverage accordingly and cement to surface. Set surface casing per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, 40 sks cement 50' above Dakota top, set 60 sks cement from 50' below J Sand base to 100' above J Sand top, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. Restore site per COGCC 1000 rules.

Attachment Check List

Att Doc Num	Name	Doc Description
400060983	FORM 2 SUBMITTED	LF@2477527 400060983
400062162	30 DAY NOTICE LETTER	LF@2477528 400062162
400062163	WELL LOCATION PLAT	LF@2477530 400062163
400062164	OIL & GAS LEASE	LF@2477531 400062164

Total Attach: 4 Files