

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE ZONE  COMMINGLE ZONE

Refiling

Sidetrack

Document Number:

400020885

Plugging Bond Surety

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: DeAnne Spector Phone: (720)876-5826 Fax: (720)876-6060

Email: deanne.spector@encana.com

7. Well Name: Federal Well Number: 20-11 (PN20)

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 6955

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 20 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.418580 Longitude: -108.022360

Footage at Surface: 1050 FNL/FSL FSL 2163 FEL/FWL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 5782 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/03/2008 PDOP Reading: 0.0 Instrument Operator's Name: Ted Taggart

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

2150 FSL 1980 FWL 2150 FSL 1980 FWL

Sec: 20 Twp: 7S Rng: 95W Sec: 20 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 2640 ft

18. Distance to nearest property line: 335 ft 19. Distance to nearest well permitted/completed in the same formation: 655 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-52	10	SW/4

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: COC01523

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bon  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
 T7S-R95W Sec 19: E2SE; Sec 20: SW/4, NW/4SE/4; Sec 21: SW/4, NW/4SE/4; Sec 22: Lots 2, 3, 4, 5, 8, 9, 10, 11 Sec 27: lots 2, 4, 5, SW/4NW/4, S/2NE/4SW/4 W/2SW/4, SE/4SW/4; Sec 28: Lots 1, 2, S/2N/2, S/2; Sec 29: All; Sec 30: Lot 3, SE/4NE/4

25. Distance to Nearest Mineral Lease Line: 589 26. Total Acres in Lease: 2532

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)?  Yes  No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal:  Offsite  Onsite

Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24+0/0	16+0/0	.25" wall	40	5	40	0
SURF	12+1/4	8+5/8	24	800	512	800	0
1ST	7+7/8	4+1/2	11.6	6,955	743	6,955	800

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments The subject well falls under the S. Parachute GAP, approved by BLM on 6/06. A copy of this GAP has been given to the COGCC for their records. Changed zone type to single, commingle to no, distance to nearest mineral lease line, and indicated this app was part of a OGLA per e-mail from DeAnne Spector 06/16/2010 RE

34. Location ID: 334682

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: DeAnne Spector

Title: Regulatory Analyst Date: 12/10/2009 Email: deanne.spector@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 6/17/2010

API NUMBER: **05 045 18708 00** Permit Number: \_\_\_\_\_ Expiration Date: 6/16/2012

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) CEMENT TOP VERIFICATION BY CBL REQUIRED.
- 4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.
- 5) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.
- 6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 280 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
400020885	FORM 2 SUBMITTED	LF@2464351 400020885
400021175	DEVIATED DRILLING PLAN	LF@2464352 400021175
400021176	DRILLING PLAN	LF@2464353 400021176
400021179	TOPO MAP	LF@2464354 400021179
400021183	ACCESS ROAD MAP	LF@2464355 400021183
400021184	LOCATION PHOTO	LF@2464356 400021184
400021190	FED. DRILLING PERMIT	LF@2464357 400021190
400021335	WELL LOCATION PLAT	LF@2464358 400021335
400021339	CONST. LAYOUT DRAWINGS	LF@2464359 400021339

Total Attach: 9 Files