

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400021362

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: DeAnne Spector Phone: (720)876-5826 Fax: (720)876-6060
Email: deanne.spector@encana.com

7. Well Name: Federal Well Number: 20-14 (PN20)

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6905

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 20 Twp: 7S Rng: 95W Meridian: 6

Latitude: 39.418520 Longitude: -108.022440

Footage at Surface: 1031 FNL/FSL FSL 2139 FEL/FWL FWL

11. Field Name: Parachute Field Number: 67350

12. Ground Elevation: 5782 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/03/2007 PDOP Reading: 0.0 Instrument Operator's Name: Ted Taggart

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 850 FSL 1980 FEL/FWL FWL Bottom Hole: FNL/FSL 850 FSL 1980 FEL/FWL FWL
Sec: 20 Twp: 7S Rng: 95W Sec: 20 Twp: 7S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2640 ft

18. Distance to nearest property line: 354 19. Distance to nearest well permitted/completed in the same formation: 510 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	440-52	10	SW/4

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC 01523

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T7S-R95W Sec 19: E2SE; Sec 20: SW/4, NW/4SE/4; Sec 21: E/2, NE/4SW/4; Sec 22: Lots 2, 3, 4, 5, 8, 9, 10, 11; Sec 27: Lots 2, 4, 5, SW/4NW/4, S/2NE/4SW/4, W/2SW/4, SE/4SW/4; Sec 28: Lots 1, 2, S/2N/2, S/2; Sec 29: All; Sec 30: Lot 3, SE/4NE/4

25. Distance to Nearest Mineral Lease Line: 683 ft 26. Total Acres in Lease: 2532

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24+0/0	16+0/0	.25 wall	40	5	40	0
SURF	12+1/4	8+5/8	24	800	512	800	0
1ST	7+7/8	4+1/2	11.6	6,907	763	6,907	800

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments The subject well falls under the S. Parachute GAP, approved by BLM on 6/2006. A copy of this GAP has been given to the COGCC for their records. Changed zone type to single, commingle to no, removed plugging bond, surface owner=mineral owner, added lease number, and indicated this app was part of a OGLA per e-mail from DeAnne Spector 06/16/2010 RE

34. Location ID: 334682

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: DeAnne Spector

Title: Regulatory Analyst Date: 12/10/2009 Email: deanne.spector@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2010

API NUMBER

05 045 18709 00

Permit Number: _____ Expiration Date: 6/16/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

5) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 280 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400021362	FORM 2 SUBMITTED	LF@2465780 400021362
400021369	PLAT	LF@2465781 400021369
400021373	TOPO MAP	LF@2465782 400021373
400021374	ACCESS ROAD MAP	LF@2465783 400021374
400021375	LOCATION PICTURES	LF@2465784 400021375
400021376	DRILLING PLAN	LF@2465785 400021376
400021377	DEVIATED DRILLING PLAN	LF@2465786 400021377
400021378	FED. DRILLING PERMIT	LF@2465787 400021378

Total Attach: 8 Files