

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2582608

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: JEVIN CROTEAU Phone: (303)623-2300 Fax: (303)623-2400

Email: JEVIN.CROTEAU@ENCANA.COM

7. Well Name: PURITAN Well Number: 4-4-34

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8331

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 34 Twp: 2N Rng: 68W Meridian: 6

Latitude: 40.093210 Longitude: -104.987370

Footage at Surface: 2017 FSL 2093 FEL

11. Field Name: SPINDLE Field Number: 77900

12. Ground Elevation: 5002 13. County: WELD

14. GPS Data:

Date of Measurement: 02/09/2010 PDOP Reading: 1.8 Instrument Operator's Name: TOM WINANS

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2610 FSL 2604 FEL 2610 FSL 2604 FEL
Sec: 34 Twp: 2N Rng: 68W Sec: 34 Twp: 2N Rng: 68W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 865 ft

18. Distance to nearest property line: 233 ft 19. Distance to nearest well permitted/completed in the same formation: 925 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SE OF SEC. 34, T2N, R68W

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	280	650	0
1ST	7+7/8	4+1/2	11.6	8,331	280	8,331	7,244

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED GWA SPACING UNIT: NWSE, NESW, SENW, SWNE Encana Oil and Gas (USA) Inc requests approval of a Rule 318Ac exception location: Wellhead is to be located more than 50' from an existing well location.

34. Location ID: 336332

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEVIN CROTEAU

Title: REGULATORY Date: 5/18/2010 Email: JEVIN.CROTEAU@ENCANA.C

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2010

API NUMBER

05 123 31748 00

Permit Number: _____ Expiration Date: 6/16/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
2582608	APD ORIGINAL	LF@2478706 2582608
2582609	WELL LOCATION PLAT	LF@2478707 2582609
2582610	TOPO MAP	LF@2478733 2582610
2582611	MINERAL LEASE MAP	LF@2478734 2582611
2582612	SURFACE AGRMT/SURETY	LF@2478708 2582612
2582613	30 DAY NOTICE LETTER	LF@2478709 2582613
2582614	DEVIATED DRILLING PLAN	LF@2478710 2582614
2582615	EXCEPTION LOC REQUEST	LF@2478711 2582615
2582616	EXCEPTION LOC WAIVERS	LF@2478712 2582616
2582617	PROPOSED SPACING UNIT	LF@2478713 2582617

Total Attach: 10 Files