

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400051902

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: Rebecca Heim Phone: (720)929-6361 Fax: (720)929-7361

Email: rebecca.heim@anadarko.com

7. Well Name: SATER Well Number: 7-8

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8023

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 8 Twp: 2N Rng: 67W Meridian: 6

Latitude: 40.153493 Longitude: -104.913529

Footage at Surface: 2466 FNL/FSL FNL 2506 FEL/FWL FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4909 13. County: WELD

14. GPS Data:

Date of Measurement: 03/18/2010 PDOP Reading: 1.6 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2130 FNL 2130 FEL 2130 FEL 2130 FNL 2130 FEL 2130
Sec: 8 Twp: 2N Rng: 67W Sec: 8 Twp: 2N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1107 ft

18. Distance to nearest property line: 178 ft 19. Distance to nearest well permitted/completed in the same formation: 678 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND	232	320	N/2
NIOBRARA-CODELL	NB-CD	407	80	W/2NE

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE ATTACHED OGL

25. Distance to Nearest Mineral Lease Line: 514 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	950	665	950	
1ST	7+7/8	4+1/2	11.6	8,023	200	8,023	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. Kerr McGee Oil & Gas Onshore LP requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Rebecca Heim

Title: Regulatory Analyst II Date: 5/17/2010 Email: DJRegulatory@anadarko.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2010

API NUMBER

05 123 31754 00

Permit Number: _____ Expiration Date: 6/16/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
400051902	FORM 2 SUBMITTED	LF@2477613 400051902
400061551	OIL & GAS LEASE	LF@2477614 400061551
400061552	MULTI-WELL PLAN	LF@2477615 400061552
400061553	DEVIATED DRILLING PLAN	LF@2477616 400061553
400061554	WELL LOCATION PLAT	LF@2477617 400061554
400061555	EXCEPTION LOC REQUEST	LF@2477618 400061555
400061556	TOPO MAP	LF@2477619 400061556
400061557	EXCEPTION LOC WAIVERS	LF@2477620 400061557
400061558	30 DAY NOTICE LETTER	LF@2477621 400061558
400061559	SURFACE AGRMT/SURETY	LF@2477622 400061559

Total Attach: 10 Files