

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400056335

Plugging Bond Surety

20040060

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BARRETT CORPORATION* BILL

4. COGCC Operator Number: 10071

5. Address: 1099 18TH ST STE 2300

City: DENVER State: CO Zip: 80202

6. Contact Name: ELAINE WINICK Phone: (303)312-8168 Fax: (303)291-0420
Email: ewinick@billbarrettcorp.com

7. Well Name: GGU Federal Well Number: 43C-29-691

8. Unit Name (if appl): Gibson Gulch Unit Number: COC-052447X

9. Proposed Total Measured Depth: 7621

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 29 Twp: 6S Rng: 91W Meridian: 6

Latitude: 39.496661 Longitude: -107.575761

Footage at Surface: 1829 FNL/FSL FSL 2074 FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 6030.7 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 03/23/2010 PDOP Reading: 2.7 Instrument Operator's Name: D. Slaugh

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2064 FSL 664 FEL FEL Bottom Hole: FNL/FSL 2064 FSL 664 FEL FEL
Sec: 29 Twp: 6S Rng: 91W Sec: 29 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 299 ft

18. Distance to nearest property line: 513 ft 19. Distance to nearest well permitted/completed in the same formation: 352 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	191-9		
Williams Fork	WMFK	191-65		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see the attached lease map

25. Distance to Nearest Mineral Lease Line: 664 ft 26. Total Acres in Lease: 600

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	42#	40		40	0
SURF	12+1/4	9+5/8	36#	800	250	800	0
1ST	8+3/4	4+1/2	11.6#	7,621	510	7,621	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments SEE ADDENDUM TO LEGAL PLAT (SHEET 2o) FOR VISIBLE IMPROVEMENTS WITHIN 400'. A NEW LOCATION ASSESSMENT HAS BEEN SUBMITTED FOR THE PROPOSED PAD EXPANSION: GGU FED (MDP #15) 34D-29-691 (DOC:400056347). IN ADDITION, THIS WELL IS APPROVED UNDER A FEDERAL ENVIRONMENTAL ASSESSMENT THROUGH THE BLM SILT, CO. OFFICE. PRODUCTION CEMENT TOP IS 500' ABOVE TOP OF SURFACE. PRODUCTINO STRING SECOND HOLE SIZE = 7 7/8.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Matt Barber

Title: Permit Analyst Date: 4/29/2010 Email: mbarber@billbarrettcorp.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2010

Permit Number: _____ Expiration Date: 6/16/2012

API NUMBER

05 045 19624 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 128 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
2557344	FED. DRILLING PERMIT	LF@2474670 2557344
400056335	FORM 2 SUBMITTED	LF@2460378 400056335
400056341	WELL LOCATION PLAT	LF@2460379 400056341
400056342	ACCESS ROAD MAP	LF@2460380 400056342
400056343	LEASE MAP	LF@2460382 400056343
400056344	LOCATION DRAWING	LF@2460383 400056344
400056345	DRILLING PLAN	LF@2460384 400056345
400056346	DEVIATED DRILLING PLAN	LF@2460385 400056346
400056431	OTHER	LF@2460386 400056431
400056702	SURFACE AGRMT/SURETY	LF@2460387 400056702

Total Attach: 10 Files