

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:

400058477

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling

Sidetrack

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8272

Email: Greg.J.Davis@Williams.com

7. Well Name: Savage Well Number: RWF 431-3

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7963

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 34 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.476339 Longitude: -107.871300

Footage at Surface: 646 FNL/FSL FSL 1818 FEL/FWL FEL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 5626 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 09/26/2008 PDOP Reading: 1.6 Instrument Operator's Name: J. Kirkpatrick

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 446 FNL 2268 FEL FEL Bottom Hole: FNL/FSL 446 FNL 2268 FEL FEL

Sec: 3 Twp: 7S Rng: 94W Sec: 3 Twp: 7S Rng: 94W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 695 ft

18. Distance to nearest property line: 604 ft 19. Distance to nearest well permitted/completed in the same formation: 295 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Williams Fork | WMFK | 139-64 | 640 | All |

21. Mineral Ownership: Fee State Federal Indian Lease #: COC
0007506

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 See Attached

25. Distance to Nearest Mineral Lease Line: 280 ft 26. Total Acres in Lease: 1595

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR | 24 | 18 | 48# | 45 | 25 | 45 | 0 |
| SURF | 13+1/2 | 9+5/8 | 32.3# | 1,102 | 385 | 1,102 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 11.6# | 7,963 | 633 | 7,963 | |

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Closed Loop. Cement 200' above uppermost mvr d sand. See Williams Master APD for drilling and surface use plans. SUA is attached to the related Form 2A. CA COC 128438 Changed commingle to no, removed plugging bond number, added federal lease number, and BOPE per verbal approval from Greg Davis 06/09/2010 RE ;

34. Location ID: 334888

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 5/4/2010 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/17/2010

| | | |
|--|----------------------|-----------------------------------|
| API NUMBER 05 045 19631 00 | Permit Number: _____ | Expiration Date: <u>6/16/2012</u> |
| CONDITIONS OF APPROVAL, IF ANY: | | |

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 250 FEET DEEP.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 250 FEET DEEP.

Attachment Check List

| Att Doc Num | Name | Doc Description |
|-------------|-------------------------|----------------------|
| 400058477 | FORM 2 SUBMITTED | LF@2464982 400058477 |
| 400059054 | WELL LOCATION PLAT | LF@2464985 400059054 |
| 400059055 | TOPO MAP | LF@2464987 400059055 |
| 400059056 | DEVIATED DRILLING PLAN | LF@2464990 400059056 |
| 400059106 | FED. DRILLING PERMIT | LF@2464995 400059106 |
| 400059511 | LEGAL/LEASE DESCRIPTION | LF@2464999 400059511 |

Total Attach: 6 Files