



State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 (303) 894-2100 Fax: (303) 894-2109



FOR OGCC USE ONLY
RECEIVED

JUN 16 2010

COGCC

LOSS OF WELL CONTROL REPORT

As required by Rule 327.

1. OGCC Operator Number: 90950	4. Contact Name & Phone	Report taken by:
2. Name of Operator: Unioil	Larry Robbins	STUART ELLSWORTH
3. Address: 1775 Sherman Street, Suite 3000	Ph: 303-860-5822	
City: Denver State: CO Zip: 80203	Fax: 303-860-5838	

WELL LOCATION INFORMATION

5. API Number: 05-123-31472	6. County: Weld
7. Well Name: Bijou	8. Well Number: 19BDU
9. Unit Name (if appl.):	10. Unit No:
11. QtrQtr: SENW Sec: 19 Twp: 5N Rng: 63W Meridian: 6th PM	
12. Footage From Exterior Section Lines: 2479 FNL, 1322 FWL	
13. Field Name: Wattenberg	14. Field Number: 90750

CASING INFORMATION

15. Surface Casing Size: 8 5/8" Weight per Foot: 24# Grade: J-55 True Vertical Setting Depth: 532'
16. Intermed. Casing Size: / Weight per Foot: Grade: True Vertical Setting Depth:

KICK INFORMATION

17. True Vertical Depth at Kick: 5789'/6039' MD	
18. Formation at Kick: Pierre Shale	19. Formation Code: PRRE
20. Shut-in Drill Pipe Pressure (SIDPP): 1000 psi	
21. Shut-in Casing Pressure (SICP): 200 psi	
22. Mud Weight at Time of Kick: 8.4 ppg	
23. Pit Gain: N/A bbls.	
24. Time and Date Shut In: 12:00 Noon June 6, 2010	
25. Mud Weight Required to Control Well: 9.4 ppg	
26. Type of Kick: <input checked="" type="checkbox"/> Gas <input type="checkbox"/> Oil <input type="checkbox"/> Water	
27. Comments (describe actions to control in detail): Rig was jetting pits and mudding up when they took the kick. SIDPP was taken after opening float, circulated out with slow pump rate and 9.4 lb/gal mud. Raised mud wt. to 10.1 lb/gal for logging operations.	