

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400061022

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Jennifer Head Phone: (303)606-4342 Fax: (303)629-8268

Email: Jennifer.Head@Williams.com

7. Well Name: Federal RG Well Number: 332-14-298

8. Unit Name (if appl): NA Unit Number: NA

9. Proposed Total Measured Depth: 11156

WELL LOCATION INFORMATION

10. QtrQtr: SWNE Sec: 14 Twp: 2S Rng: 98W Meridian: 6

Latitude: 39.880280 Longitude: -108.358300

Footage at Surface: 1767 FNL/FSL FNL 2254 FEL/FWL FEL

11. Field Name: Sulphur Creek Field Number: 80090

12. Ground Elevation: 6546.6 13. County: RIO BLANCO

14. GPS Data:

Date of Measurement: 02/03/2010 PDOP Reading: 0.9 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1655 FNL 1930 FEL 1655 FNL 1930 FEL  
Sec: 14 Twp: 2S Rng: 98W Sec: 14 Twp: 2S Rng: 98W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 3785 ft

18. Distance to nearest property line: 2971 ft 19. Distance to nearest well permitted/completed in the same formation: 285 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	527-6		
Sego	SEGO	527-6		
Williams Fork	WMFK	527-6		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC 066586

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T2S, R98W, Section 14: SE Qtr, W/2 SE Qtr, Lots 2-7

25. Distance to Nearest Mineral Lease Line: 607 ft 26. Total Acres in Lease: 666

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation & Backfilling

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	18	48#	80	135	80	0
SURF	14+3/4	9+5/8	36#	3,010		3,010	0
3RD	8+3/4	4+1/2	11.6#	11,156		11,156	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Cement will be circulated to the surface in the Conductor String. Cement will be circulated to 200' above the uppermost Mesaverde sand in the Production String, will be expanded.

34. Location ID: 335988

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Jennifer Head

Title: Regulatory Team Lead Date: 5/13/2010 Email: Jennifer.Head@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/25/2010

#### API NUMBER

05 103 11752 00

Permit Number: \_\_\_\_\_ Expiration Date: 6/24/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) CEMENT TOP VERIFICATION BY CBL REQUIRED.

3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
400061022	FORM 2 SUBMITTED	LF@2477305 400061022
400061390	WELL LOCATION PLAT	LF@2477306 400061390
400061391	TOPO MAP	LF@2477307 400061391
400061392	DEVIATED DRILLING PLAN	LF@2477308 400061392
400061697	FED. DRILLING PERMIT	LF@2477309 400061697

Total Attach: 5 Files