

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400064619

Plugging Bond Surety

20070004

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY LLC

4. COGCC Operator Number: 8960

5. Address: P O BOX 21974

City: BAKERSFIELD State: CA Zip: 93390

6. Contact Name: Keith Caplan Phone: (720)279-2330 Fax: (720)279-2331

Email: KCaplan@bonanzacrk.com

7. Well Name: Antelope Well Number: 44-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 6850

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 19 Twp: 5N Rng: 62W Meridian: 6

Latitude: 40.379260 Longitude: -104.359020

Footage at Surface: 660 FNL/FSL 660 FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4662 13. County: WELD

14. GPS Data:

Date of Measurement: 05/18/2010 PDOP Reading: 2.4 Instrument Operator's Name: Dan Griggs

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2700 ft

18. Distance to nearest property line: 660 19. Distance to nearest well permitted/completed in the same formation: 1320

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara-Codell	NB-CD		160	SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20070001

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
please see attached

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 5266

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	425	240	425	0
1ST	7+7/8	4+1/2	11.6	6,850	200	6,850	6,000

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used on this well.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Stephen Wolfe

Title: Sr. Prod. Eng. Date: 5/28/2010 Email: srw@bonanzacrk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nashin Director of COGCC Date: 6/27/2010

API NUMBER

05 123 31809 00

Permit Number: _____ Expiration Date: 6/26/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) If dry hole, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. Restore surface location.

Attachment Check List

Att Doc Num	Name	Doc Description
1725849	SURFACE CASING CHECK	LF@2489896 1725849
400064619	FORM 2 SUBMITTED	LF@2484327 400064619
400064661	LEGAL/LEASE DESCRIPTION	LF@2484328 400064661
400066437	PLAT	LF@2484329 400066437

Total Attach: 4 Files