

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐
Refiling ☐Sidetrack ☐

Document Number:

400071860

Plugging Bond Surety

20100017

3. Name of Operator: ENCANA OIL &amp; GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240

Email: Julia.Carter@encana.com

7. Well Name: SGU Well Number: 8514D-24 F25496

8. Unit Name (if appl): Big Jimmy Unit Unit Number: COC74105X

9. Proposed Total Measured Depth: 14203

## WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 25 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.674403 Longitude: -108.119514

 Footage at Surface: 2246 FNL/FSL 1977 FEL/FWL  
 FNL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 8298 13. County: GARFIELD

## 14. GPS Data:

Date of Measurement: 08/07/2009 PDOP Reading: 1.4 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
 268 FSL 2082 FWL 268 FSL 2082 FWL  
 Sec: 24 Twp: 4S Rng: 96W Sec: 24 Twp: 4S Rng: 96W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 437 ft

18. Distance to nearest property line: 1977 ft 19. Distance to nearest well permitted/completed in the same formation: 344 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Williams Fork	WMFK	510-13	10	

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC64814

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4S, R96W, 6th PM, Sec 22: Lots 1-6, E2NE, NW, S2S2; Sec 23: Lot 1, 2, 4-8, NE, W2NW, S2SW, SWSE; Sec 24: Lot 1-4, S2N2, S2; Sec 26: NW; Sec 27: N2

25. Distance to Nearest Mineral Lease Line: 268 ft 26. Total Acres in Lease: 2425

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle, Amend and Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	20	Line Pipe	120	176	120	0
SURF	14+3/4	9+5/8	36	3,000	1,047	3,000	0
1ST	7+7/8	4+1/2	11.6	14,203	645	14,203	8,543

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana Oil & Gas (USA) Inc. owns surface. Please note cement will be run to surface for both conductor and surface casing. The surface casing hole size will be 14-3/4", 12-1/4" or 13-1/2". Production casing hole size will be both 7-7/8" and 8-3/4". Production cement top calculation 500' above TOG. Onsite was on 8/12/2009 with BLM and CDOW.

34. Location ID: 415182

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: \_\_\_\_\_ Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400071959	PLAT	SGU 8514D-24 F25 496.Plat.pdf
400071960	DEVIATED DRILLING PLAN	SGU 8514D-24 F25 496.DirectionaI Plan.pdf
400071961	MINERAL LEASE MAP	Big Jimmy Unit Mineral Ownership.pdf
400071963	TOPO MAP	SGU F25 496.Topo Maps.pdf
400072920	FED. DRILLING PERMIT	SGU 8514D-24 F25 496.Federal APD.pdf

Total Attach: 5 Files