

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400056279

Plugging Bond Surety

20030107

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8272

Email: Greg.J.Davis@Williams.com

7. Well Name: ExxonMobil Well Number: GM 344-27

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7304

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 27 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.493206 Longitude: -108.089928

Footage at Surface: 1921 FNL/FSL FSL 1334 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 5655 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/17/2008 PDOP Reading: 1.9 Instrument Operator's Name: Kurt Shepherd

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 774 FSL 438 FEL FEL Bottom Hole: FNL/FSL 774 FSL 438 FEL FEL
Sec: 27 Twp: 6S Rng: 96W Sec: 27 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 4213 ft

18. Distance to nearest property line: 722 ft 19. Distance to nearest well permitted/completed in the same formation: 361 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	479-12	320	S/2

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: CA
COC49009

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
 See Attached

25. Distance to Nearest Mineral Lease Line: 438 ft 26. Total Acres in Lease: 283

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48#	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	980	345	980	0
1ST	7+7/8	4+1/2	11.6#	7,304	560	7,304	

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Closed Loop. Cement 200' above uppermost mvrd sand. See Williams Master APD for drilling and surface use plans. SUA attached with related Form 2A.

34. Location ID: 323789

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 5/17/2010 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 6/29/2010

API NUMBER

05 045 19669 00

Permit Number: _____ Expiration Date: 6/28/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)CEMENT TOP VERIFICATION BY CBL REQUIRED.

4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 130 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
1791620	SURFACE AGRMT/SURETY	LF@2498440 1791620
400056279	FORM 2 SUBMITTED	LF@2478529 400056279
400056772	LEGAL/LEASE DESCRIPTION	LF@2478530 400056772
400059561	WELL LOCATION PLAT	LF@2478531 400059561
400059562	TOPO MAP	LF@2478532 400059562
400060021	DEVIATED DRILLING PLAN	LF@2478533 400060021
400062390	FED. DRILLING PERMIT	LF@2478534 400062390

Total Attach: 7 Files