

WELL LOCATION CERTIFICATE

NW CRN SEC. 21
2.5°AC LS 23513

SECTION 21, TOWNSHIP 4 NORTH, RANGE 67 WEST, 6TH P.M.
S89°17'39"E 2683.2'

N1/4 CRN SEC. 21
3.25°AC LS 16427

BASIS OF BEARINGS

2631.7'

S01°12'17"E

2633.3'

N01°12'47"W

W1/4 CRN SEC. 21
2.5°AC LS 30462

SW CRN SEC. 21
3.25°AC LS 7242

S89°29'31"E 2668.3'

S1/4 CRN SEC. 21
2.5°AC LS 22097

NOTES:

THIS IS A DIRECTIONAL DRILL WELL.
BOTTOM HOLE AT 2577' FSL, 2624' FWL.

WELL FALLS IN A PLOWED FIELD.
A PROPOSED WELL IS 22' SW.
SEE LOCATION DRAWING FOR IMPROVEMENTS.

GROUND ELEVATION = 4940'
LAT. & LONG. = N 40.29550°
W 104.89954°

BH = 2577' FSL,
2624' FWL.

1657'


1589'

N44°03'E
1363'

I HEREBY STATE TO UNIOIL THAT THIS WELL LOCATION CERTIFICATE FOR THE WELL WALTERS 21-ODU IS LOCATED 1589' FSL & 1657' FWL, SEC. 21, T4N, R67W, 6PM.

LEGEND

-  = FOUND MONUMENT
-  = PROPOSED WELL
-  = BOTTOM HOLE



SCALE 1" = 1000'

ELEVATION SOURCE = USGS 7.5' QUAD.MAP CONTOURS
NGVD 1929 DATUM.

LAT. & LONG. ARE DIFFERENTIALLY CORRECTED (NAD'83)
USING (DGPS) WITH (PDOP) VALUES LESS THAN SIX (6).

SHOWN DISTANCES ARE FIELD MEASURED - EXTERIOR SECTION LINES
ARE DRAWN TO SCALE (BEST APPROX. OR FOUND MONUMENT ).

DISTANCES TO WELL SHOWN PERPENDICULAR
TO SECTION LINES.

THOMAS G. CARLSON, PLS 24657
HORSESHOE SURVEYING, LLC

THIS IS NOT A MONUMENTED BOUNDARY SURVEY, IT IS ONLY A
DRAWING INTENDED TO DEPICT THE WELL LOCATION TO SECTION LINES.

PREPARED BY:	HORSESHOE SURVEYING, LLC PO BOX 150458 LAKEWOOD, CO 80215 (720)872-0196	WELL NAME:	WALTERS 21-ODU
DRAWING DATE: 3-11-10		LOCATION:	WELD COUNTY, CO SW1/4, SEC. 21, T4N, R67W, 6TH P.M.
FIELD DATE: 3-10-10	BY: TGC	CHKD:	JOB NO. SHEET NO. 1 OF 1

