

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400055058
Plugging Bond Surety
20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY 4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000
City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8272
Email: Greg.J.Davis@Williams.com

7. Well Name: Jolley Well Number: KP 32-21

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8009

WELL LOCATION INFORMATION

10. QtrQtr: SENW Sec: 21 Twp: 6S Rng: 91W Meridian: 6
Latitude: 39.515606 Longitude: -107.560984

Footage at Surface: 1869 FNL/FSL FNL 2201 FEL/FWL FWL

11. Field Name: Kokopelli Field Number: 47525

12. Ground Elevation: 6889 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/24/2009 PDOP Reading: 1.7 Instrument Operator's Name: J. Kirkpatrick

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1466 FNL 1977 FEL 1466 FNL 1977 FEL
Sec: 21 Twp: 6S Rng: 91W Sec: 21 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 3089 ft

18. Distance to nearest property line: 554 ft 19. Distance to nearest well permitted/completed in the same formation: 334 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES	513-4		
Williams Fork	WMFK	513-4		

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached

25. Distance to Nearest Mineral Lease Line: 153 ft 26. Total Acres in Lease: 320

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite

Method: Land Farming Land Spreading Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48#	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	801	280	801	0
1ST	7+7/8	4+1/2	11.6#	8,009	650	8,009	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Closed Loop. Cement 500' above top of gas. Well was originally permitted by Orion Energy Partners LP. Refile reflects changes to surface, bottomhole and drilling plans. New plats, directional plot and plan attached. This is an existing pad that is not fully developed. There have been no changes to lease conditions since the original Form 2 was filed. No rig on location. Changed commingle to yes and added rotating head to BOPE per e-mail from Greg Davis 06/23/2010 RE

34. Location ID: 335209

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 5/10/2010 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 7/2/2010

Permit Number: _____ Expiration Date: 7/1/2012

API NUMBER

05 045 17998 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 160 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400055058	FORM 2 SUBMITTED	LF@2468413 400055058
400059789	WELL LOCATION PLAT	LF@2468415 400059789
400059790	TOPO MAP	LF@2468417 400059790
400059796	DEVIATED DRILLING PLAN	LF@2468422 400059796
400059832	LEGAL/LEASE DESCRIPTION	LF@2468424 400059832

Total Attach: 5 Files