

LDS D17-17
T3N, R64W 6th P.M.
Section 17: SWNE

Map Unit Description

Weld County, Colorado, Southern Part

50 Otero sandy loam, 0 to 1 percent slopes

Setting

Elevation: 4700 to 5250 feet
Mean annual precipitation: 12 to 15 inches
Mean annual air temperature: 48 to 52 degrees F
Frost-free period: 130 to 180 days

Composition

Otero and similar soils: 85 percent
Minor components: 15 percent

Description of Otero

Setting

Landform: Plains
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Eolian deposits and/or mixed outwash

Properties and Qualities

Slope: 0 to 1 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.57 to 5.95 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 10 percent
Gypsum maximum: 0 percent
Available water capacity: Moderate (about 7.7 inches)

Interpretive Groups

Land capability classification (irrigated): 3e
Ecological site: Sandy Plains (R067BY024CO)

Typical Profile

0 to 12 inches: sandy loam
12 to 60 inches: fine sandy loam

Minor Components

Haverson

Percent of map unit: 8 percent

Kim

Percent of map unit: 7 percent

LDS D17-17
T3N, R64W 6th P.M.
Section 17: SWNE

Map Unit Description

Weld County, Colorado, Southern Part

25 Haverson loam, 0 to 1 percent slopes

Setting

Elevation: 4500 to 4800 feet
Mean annual precipitation: 12 to 17 inches
Mean annual air temperature: 46 to 54 degrees F
Frost-free period: 125 to 180 days

Composition

Haverson and similar soils: 85 percent
Minor components: 15 percent

Description of Haverson

Setting

Landform: Flood plains, stream terraces
Down-slope shape: Linear
Across-slope shape: Linear
Parent material: Stratified, calcareous alluvium

Properties and Qualities

Slope: 0 to 1 percent
Drainage class: Well drained
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.60 to 2.00 in/hr)
Frequency of flooding: None
Frequency of ponding: None
Calcium carbonate maximum: 15 percent
Gypsum maximum: 1 percent
Available water capacity: High (about 9.6 inches)

Interpretive Groups

Land capability classification (irrigated): 3w
Ecological site: Loamy Plains (R067BY002CO)

Typical Profile

0 to 4 inches: loam
4 to 60 inches: stratified loamy sand to loam to clay loam

Minor Components

Vona

Percent of map unit: 8 percent

Fluvaquentic haplustolls

Percent of map unit: 4 percent
Landform: Terraces

Other soils

Percent of map unit: 3 percent