

FORM
2
Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling
Sidetrack

Document Number:
400060564
Plugging Bond Surety
20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION 4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000
City: DENVER State: CO Zip: 80203

6. Contact Name: Kelly Huffman Phone: (303)831-3974 Fax: (303)860-5838
Email: khuffman@petd.com

7. Well Name: Bauer Debus Well Number: 22MD

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7033

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 22 Twp: 5N Rng: 64W Meridian: 6
Latitude: 40.390500 Longitude: -104.538560

Footage at Surface: 587 FNL/FSL FNL 1920 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4575 13. County: WELD

14. GPS Data:

Date of Measurement: 04/08/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G. Carlson

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 25 FNL 2644 FWL FWL Bottom Hole: FNL/FSL 25 FNL 2644 FWL FWL
Sec: 22 Twp: 5N Rng: 64W Sec: 22 Twp: 5N Rng: 64W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 572 ft

18. Distance to nearest property line: 587 ft 19. Distance to nearest well permitted/completed in the same formation: 825 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara Codell	NB-CD	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Please see attached map

25. Distance to Nearest Mineral Lease Line: 25 ft 26. Total Acres in Lease: 117

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	390	650	0
1ST	7+7/8	4+1/2	10.5	7,033	116	7,033	5,633
S.C. 1.1	7+7/8	4+1/2	10.5	7,033	116	7,033	5,633

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Conductor casing will not be used. The Bauer Debus well will be drilled from the same pad as the Bauer Debus 22ND, 22JD and 22AD wells. The well will be tied into the Bauer Debus tank battery which will be added to the existing tank battery facility located at the Joshua #1 well. Operator requests approval of an exception location to rule 318Ac. Waiver attached. Proposed spacing unit is nenw, nwnw sec 22; swse, sesw sec 15

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelly Huffman

Title: Contract Land Technician Date: 6/14/2010 Email: khuffman@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/14/2010

API NUMBER
05 123 31865 00

Permit Number: _____ Expiration Date: 7/13/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us .
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
1725966	SURFACE CASING CHECK	LF@2497696 1725966
400060564	FORM 2 SUBMITTED	LF@2490070 400060564
400062675	WELL LOCATION PLAT	LF@2490071 400062675
400062676	TOPO MAP	LF@2490072 400062676
400062677	DEVIATED DRILLING PLAN	LF@2490073 400062677
400062713	UNIT CONFIGURATION MAP	LF@2490074 400062713
400066094	30 DAY NOTICE LETTER	LF@2490075 400066094
400066096	EXCEPTION LOC REQUEST	LF@2490076 400066096
400068223	EXCEPTION LOC WAIVERS	LF@2490077 400068223
400068224	30 DAY NOTICE LETTER	LF@2490078 400068224
400068231	LEASE MAP	LF@2490079 400068231

Total Attach: 11 Files