

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



| | | | |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:

2557556

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: WEXPRO COMPANY

4. COGCC Operator Number: 95960

5. Address: P O BOX 45003

City: SALT LAKE CITY State: UT Zip: 84145-0601

6. Contact Name: DEE FINDLAY Phone: (801)324-2600 Fax: (801)324-2637
Email: DEE.FINDLAY@QUESTAR.COM

7. Well Name: JACKS DRAW Well Number: 19

8. Unit Name (if appl): JACKS DRAW Unit Number: COC47639A

9. Proposed Total Measured Depth: 9356

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 10 Twp: 11N Rng: 97W Meridian: 6

Latitude: 40.924289 Longitude: -108.276147

Footage at Surface: 1342 FNL/FSL FSL 2264 FEL/FWL FEL

11. Field Name: POWDER WASH Field Number: 69800

12. Ground Elevation: 6894 13. County: MOFFAT

14. GPS Data:

Date of Measurement: 06/01/2009 PDOP Reading: 2.2 Instrument Operator's Name: MCCOY ANDERSON

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 210 ft

18. Distance to nearest property line: 2 mi 19. Distance to nearest well permitted/completed in the same formation: 1329 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| FORT UNION | FTUN | | | |
| WASATCH | WSTC | | | |

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COD005289
7

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED MAP

25. Distance to Nearest Mineral Lease Line: 375 ft 26. Total Acres in Lease: 440

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: RESERVE PIT

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR | 26 | 20 | | 80 | 8 | 80 | 0 |
| SURF | 12+1/4 | 9+5/8 | 36 | 500 | 284 | 500 | 0 |
| 1ST | 7+7/8 | 4+1/2 | 13.5 | 9,356 | 1,302 | 9,356 | 0 |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments THIS WELL IS COVERED BY THE MASTER SURFACE USE PLAN FOR POWDER WASH AND JACKS DRAW UNIT WELLS DATED 01-01-10.

34. Location ID: 416425

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: G.T. NIMMO

Title: OPERATIONS MGR Date: 5/27/2010 Email: DEE.FINDLAY@QUESTAR.CO

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/15/2010

API NUMBER

05 081 07616 00

Permit Number: _____ Expiration Date: 7/14/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)CEMENT TOP VERIFICATION BY CBL REQUIRED.

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

| Att Doc Num | Name | Doc Description |
|-------------|----------------------|--------------------|
| 2557556 | APD ORIGINAL | LF@2483652 2557556 |
| 2557557 | WELL LOCATION PLAT | LF@2483653 2557557 |
| 2557558 | LOCATION DRAWING | LF@2483654 2557558 |
| 2557559 | TOPO MAP | LF@2483719 2557559 |
| 2557560 | MINERAL LEASE MAP | LF@2483720 2557560 |
| 2557561 | FED. DRILLING PERMIT | LF@2483655 2557561 |

Total Attach: 6 Files