

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☒

Sidetrack ☐

Document Number:

400054164

Plugging Bond Surety

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: JANNI KEIDEL Phone: (303)999-4225 Fax: (303)999-4325

Email: jek@bry.com

7. Well Name: SCHOOL HOUSE POINT Well Number: OM13C A21 696

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 10195

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 21 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.515181 Longitude: -108.105631

Footage at Surface: 210 FNL/FSL FNL 269 FEL/FWL FEL

11. Field Name: PARACHUTE Field Number: 67350

12. Ground Elevation: 8313 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 05/04/2007 PDOP Reading: 2.2 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 300 FSL 340 FWL 300 FSL 340 FWL  
Sec: 15 Twp: 6S Rng: 96W Sec: 15 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 5773 ft

18. Distance to nearest property line: 2442 ft 19. Distance to nearest well permitted/completed in the same formation: 473 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE MINERAL LEASE MAP ATTACHED TO ORIGINAL APD

25. Distance to Nearest Mineral Lease Line: 2982 ft 26. Total Acres in Lease: 25000

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
3RD	8+3/4	4+1/2	11.6	10,195	600	10,195	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there have been no changes on land use, lease description. Pad has been built. Pit has been constructed and lined per COGCC rules. 1 Well has been drilled. Conductors have been set. No rig on site. The refile will not require any expansion / additional surface disturbance of pad. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is not in a sensitive wildlife habitat area. The production casing Top of Cement will be a minimum of 200' above the Top of Gas.

34. Location ID: 335516

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JANNI KEIDEL

Title: PERMITTING AGENT Date: 6/12/2010 Email: jek@bry.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 7/21/2010

Permit Number: \_\_\_\_\_ Expiration Date: 7/20/2011

**API NUMBER**

05 045 14962 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLY WITH NOTIFICATION REQUIREMENTS OF THE MOST CURRENT VERSION OF THE NORTHWEST COLORADO NOTIFICATION POLICY.

24-HOUR NOTICE TO MOVE ON LOCATION REQUIRED. E-MAIL: Mike.Longworth@state.co.us

Also E-MAIL: Shaun.Kellerby@state.co.us

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) CEMENT-TOP VERIFICATION BY CBL REQUIRED.

(4) THE NEARBY HILLSIDE MUST BE MONITORED FOR ANY DAY-LIGHTING DRILLING FLUIDS THROUGHOUT THE DRILLING OF THE SURFACE-CASING INTERVAL.

(5) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN  $\frac{3}{4}$  MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY -- PIT DESIGN, CONSTRUCTION, AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.

(6) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400054164	FORM 2 SUBMITTED	LF@2491342 400054164
400068842	30 DAY NOTICE LETTER	LF@2491343 400068842

Total Attach: 2 Files