

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400068850

Plugging Bond Surety

20040105

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling

Sidetrack

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: JANNI KEIDEL Phone: (303)999-4225 Fax: (303)999-4325

Email: jek@bry.com

7. Well Name: GRANLEE OM Well Number: 08D 102 696

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11571

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 2 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.553642 Longitude: -108.068522

Footage at Surface: 3434 FNL/FSL FNL 331 FEL/FWL FEL

11. Field Name: GRAND VALLEY Field Number: 31290

12. Ground Elevation: 8435 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/09/2006 PDOP Reading: 1.5 Instrument Operator's Name: ROBERT KAY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2495 FNL 502 FEL 502 FEL 2495 FNL 502 FEL 502

Sec: 2 Twp: 6S Rng: 96W Sec: 2 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 26400 ft

18. Distance to nearest property line: 690 ft 19. Distance to nearest well permitted/completed in the same formation: 407 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE MINERAL LEASE MAP ATTACHED TO ORIGINAL APD.

25. Distance to Nearest Mineral Lease Line: 1640 ft 26. Total Acres in Lease: 25000

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
3RD	8+3/4	4+1/2	11.6	11,571	600	11,571	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments I certify that there have been no changes on land use, lease description. Pad has been built. Pit has been constructed. Wells have been drilled. Conductors have been set. No rig on site. The refile will not require any expansion / additional surface disturbance of pad. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is in a sensitive wildlife habitat area for Elk Production. The production casing Top of Cement will be a minimum of 200' above the Top of Gas.

34. Location ID: 335617

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JANNI KEIDEL

Title: PERMITTING AGENT Date: 6/12/2010 Email: jek@bry.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 7/22/2010

Permit Number: _____ Expiration Date: 7/21/2011

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLY WITH NOTIFICATION REQUIREMENTS OF THE MOST CURRENT VERSION OF THE NORTHWEST COLORADO NOTIFICATION POLICY.

24-HOUR NOTICE TO MOVE ON LOCATION REQUIRED. E-MAIL: Mike.Longworth@state.co.us

Also E-MAIL: Shaun.Kellerby@state.co.us

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) CEMENT-TOP VERIFICATION BY CBL REQUIRED.

(4) RESERVE PIT MUST BE LINED.

(5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(6) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(7) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400068850	FORM 2 SUBMITTED	LF@2490427 400068850
400068852	30 DAY NOTICE LETTER	LF@2490428 400068852

Total Attach: 2 Files