

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400077952

Plugging Bond Surety

20060137

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐Refiling ☐Sidetrack ☐3. Name of Operator: OXY USA WTP LP4. COGCC Operator Number: 665715. Address: P O BOX 27757City: HOUSTON State: TX Zip: 772276. Contact Name: Joan Proulx Phone: (970)263.3641 Fax: (970)263.3694Email: joan_proulx@oxy.com7. Well Name: Cascade Creek Well Number: 697-08-29C

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8975

WELL LOCATION INFORMATION

10. QtrQtr: NESE Sec: 8 Twp: 6S Rng: 97W Meridian: 6Latitude: 39.536004 Longitude: -108.237731

		FNL/FSL		FEL/FWL
Footage at Surface:	<u>2115</u>	<u>FSL</u>	<u>1009</u>	<u>FEL</u>

11. Field Name: Grand Valley Field Number: 3129012. Ground Elevation: 8479 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 07/01/2010 PDOP Reading: 1.9 Instrument Operator's Name: John Richardson15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:	FNL/FSL	FEL/FWL	Bottom Hole:	FNL/FSL	FEL/FWL
<u>2580</u>	<u>FSL</u>	<u>2308</u>	<u>2580</u>	<u>FSL</u>	<u>2308</u>
Sec: <u>8</u>	Twp: <u>6S</u>	Rng: <u>97W</u>	Sec: <u>8</u>	Twp: <u>6S</u>	Rng: <u>97W</u>

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 3754 ft18. Distance to nearest property line: 3492 ft 19. Distance to nearest well permitted/completed in the same formation: 328 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-15		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See attached Mineral Lease Description

25. Distance to Nearest Mineral Lease Line: 4313 ft 26. Total Acres in Lease: 9520

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Onsite reserve pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20+0/0	16+0/0	65#	100		100	
SURF	14+3/4	9+5/8	36#	2,690	1,420	2,690	
1ST	8+3/4	4+1/2	11.6#	8,965	2,094	8,965	5,595

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Oxy is both the surface and mineral owner. Rule 305 and 306 are waived. The well pad has been constructed and there is one producing well on this location; there is currently no drilling rig on this pad. Drilling operations are projected to commence sometime in early 2011. A semi-closed loop system will be used. Per GarCo Vacation Ordinance dated 10-5-1987, CR 213 is now OXY's private property north of Sec 8, 7S, 97W, 6 PM. Oxy will comply with new "Notice to Operators" regarding reserve pits (June 12, 2008). Oxy will provide appropriate housing for essential personnel in order to conduct safe, efficient drilling operations at this well site.

34. Location ID: 324296

35. Is this application in a Comprehensive Drilling Plan? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Joan Proulx

Title: Regulatory Analyst Date: _____ Email: joan_proulx@oxy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400078434	MINERAL LEASE MAP	Mineral lease description.PDF
400078435	TOPO MAP	608-43-31 Topo.PDF
400078436	WELL LOCATION PLAT	697-08-29C Plat.PDF
400078437	DEVIATED DRILLING PLAN	CC 697-08-29C Plan 1.pdf

Total Attach: 4 Files