

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2558212

Plugging Bond Surety

20090080

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: GREAT WESTERN OIL & GAS COMPANY LLC

4. COGCC Operator Number: 10110

5. Address: 503 MAIN ST

City: WINDSOR State: CO Zip: 80550

6. Contact Name: JEFF REALE Phone: (970)686-8831 Fax: (866)413-3354

Email: JREALE@GWOGCO.COM

7. Well Name: COULSON Well Number: 2-14

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7550

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 2 Twp: 4N Rng: 67W Meridian: 6

Latitude: 40.337360 Longitude: -104.862110

Footage at Surface: 1266 FNL/FSL FSL 1567 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4740 13. County: WELD

14. GPS Data:

Date of Measurement: 04/12/2010 PDOP Reading: 2.1 Instrument Operator's Name: E. HERNANDEZ

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 657 FSL 668 FEL/FWL FWL Bottom Hole: FNL/FSL 657 FSL 668 FEL/FWL FWL  
Sec: 2 Twp: 4N Rng: 67W Sec: 2 Twp: 4N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 289 ft

18. Distance to nearest property line: 40 ft 19. Distance to nearest well permitted/completed in the same formation: 2786 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD	407-87	80	W/2SW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEE ATTACHED EXHIBIT A

25. Distance to Nearest Mineral Lease Line: 134 ft 26. Total Acres in Lease: 74

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	460	265	460	0
1ST	7+7/8	4+1/2	11.6	7,550	200	7,550	6,400

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE SET. 30 DAY NOTICE WAIVER IN SUA. Great Western Oil & Gas Company LLC requests approval of a Rule 603.a.(2) exception location: Wellhead is to be located less than 150' from a property line.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JEFF REALE

Title: VP OPERATIONS Date: 6/16/2010 Email: JREALE@GWOGCO.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/23/2010

#### API NUMBER

05 123 31934 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/22/2012

#### CONDITIONS OF APPROVAL, IF ANY:

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- 1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from end of production casing to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name	Doc Description
2558212	APD ORIGINAL	LF@2494074 2558212
2558213	MINERAL LEASE MAP	LF@2494052 2558213
2558214	WELL LOCATION PLAT	LF@2494075 2558214
2558215	TOPO MAP	LF@2494051 2558215
2558216	EXCEPTION LOC REQUEST	LF@2494076 2558216
2558217	EXCEPTION LOC WAIVERS	LF@2494077 2558217
2558218	SURFACE AGRMT/SURETY	LF@2494078 2558218
2558219	ACCESS ROAD MAP	LF@2494050 2558219
2558220	DEVIATED DRILLING PLAN	LF@2494079 2558220
2558221	OTHER	LF@2494080 2558221

Total Attach: 10 Files