

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400069640

Plugging Bond Surety

20100017

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240
Email: Julia.Carter@encana.com

7. Well Name: N. Parachute Well Number: MF06B-16 H17 69

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9382

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 17 Twp: 6S Rng: 96W Meridian: 6

Latitude: 39.527414 Longitude: -108.123542

Footage at Surface: 1548 FNL/FSL FNL 292 FEL/FWL FEL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 5654 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/16/2007 PDOP Reading: 1.6 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1711 FNL 1394 FWL 1711 FNL 1394 FWL
Sec: 16 Twp: 6S Rng: 96W Sec: 16 Twp: 6S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 450 ft

18. Distance to nearest property line: 292 ft 19. Distance to nearest well permitted/completed in the same formation: 283 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	510-8		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Maps on file

25. Distance to Nearest Mineral Lease Line: 1394 ft 26. Total Acres in Lease: 25889

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	26	16	Line Pipe	90	8	90	0
SURF	13+1/2	9+5/8	36	1,300	253	1,300	0
1ST	7+7/8	4+1/2	11.6	9,382	616	9,382	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This is a refile - API# 05-045-18705. This pad has been built, no pit will be used, there will be no additional surface disturbance, the location does not require any variance and it is not in a wildlife restricted surface occupancy area. Therefore, a Form 2A will not be submitted. Chevron USA owns surface, Encana minerals. Pursuant to Order 510-8 the following documents were filed with the COGCC when this well was first permitted: reclamation plan guideline, wellsite diagrams, interim and final reclamation figures and a reclamation schedule. Surface Owners Agreement is also on file at the COGCC. Please note cement will be run to surface for both conductor and surface casing. Surface casing hole size will be 13-1/2" and 12-1/4". Production casing hole size will be 7-7/8", 8-1/2" and 8-3/4" with cement set 200' above WMFK.

34. Location ID: 335825

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 6/16/2010 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/27/2010

Permit Number: _____ Expiration Date: 7/26/2011

API NUMBER

05 045 18705 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 74 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400069640	FORM 2 SUBMITTED	LF@2491437 400069640

Total Attach: 1 Files