

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400058971

Plugging Bond Surety

20040105

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: JANNI KEIDEL Phone: (303)999-4225 Fax: (303)999-4325

Email: jek@bry.com

7. Well Name: MILK CABIN Well Number: OM16A P32 595

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11946

WELL LOCATION INFORMATION

10. QtrQtr: SESE Sec: 32 Twp: 5S Rng: 95W Meridian: 6

Latitude: 39.565511 Longitude: -108.070181

Footage at Surface: 891 FNL/FSL FSL 439 FEL/FWL FEL

11. Field Name: PARACHUTE Field Number: 67350

12. Ground Elevation: 8357 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/31/2006 PDOP Reading: 2.6 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1308 FSL 337 FEL FEL Bottom Hole: FNL/FSL 1308 FSL 337 FEL FEL  
Sec: 32 Twp: 5S Rng: 95W Sec: 32 Twp: 5S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 10560 ft

18. Distance to nearest property line: 6125 ft 19. Distance to nearest well permitted/completed in the same formation: 291 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
PLEASE SEE MINERAL LEASE MAP ATTACHED TO ORIGINAL APD.

25. Distance to Nearest Mineral Lease Line: 6140 ft 26. Total Acres in Lease: 25000

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
3RD	8+3/4	4+1/2	11.6	11,946	600	11,946	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there have been no changes on land use, lease description. Pad has been built. Pit has been constructed. Wells have not been drilled. Conductors have not been set. No rig on site. The refile will not require any expansion / additional surface disturbance of pad. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is in a sensitive wildlife habitat area for Elk production. The production casing Top of Cement will be 200' or more above the Top of Gas.

34. Location ID: 413574

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: JANNI KEIDEL

Title: PERMITTING AGENT Date: 6/14/2010 Email: jek@bry.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 7/28/2010

Permit Number: \_\_\_\_\_ Expiration Date: 7/27/2012

**API NUMBER**

05 045 18671 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.

5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400058971	FORM 2 SUBMITTED	LF@2491402 400058971
400068877	30 DAY NOTICE LETTER	LF@2491403 400068877
400068927	ACCESS ROAD MAP	LF@2491404 400068927
400068928	DEVIATED DRILLING PLAN	LF@2491405 400068928
400068929	MINERAL LEASE MAP	LF@2491406 400068929
400068930	WELL LOCATION PLAT	LF@2491407 400068930

Total Attach: 6 Files