

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☐ COALBED ☒ OTHER _____
 SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☒Sidetrack ☐

Document Number:

400080366

Plugging Bond Surety

20040083

3. Name of Operator: PIONEER NATURAL RESOURCES USA INC4. COGCC Operator Number: 100845. Address: 1401 17TH ST STE 1200City: DENVER State: CO Zip: 802026. Contact Name: Georgina Kovacic Phone: (303)675-2611 Fax: (303)294-1251Email: georgina.kovacic@pxd.com7. Well Name: WOOD Well Number: 31-2 R8. Unit Name (if appl): NA Unit Number: NA9. Proposed Total Measured Depth: 2325

WELL LOCATION INFORMATION

10. QtrQtr: NW/NE Sec: 2 Twp: 33S Rng: 68W Meridian: 6Latitude: 37.205060 Longitude: -104.960490
 Footage at Surface: 906 FNL/FSL FNL 1399 FEL/FWL FEL
11. Field Name: Purgatoire River Field Number: 7083012. Ground Elevation: 8193 13. County: LAS ANIMAS

14. GPS Data:

Date of Measurement: 04/19/2010 PDOP Reading: 0.0 Instrument Operator's Name: R. Coberly15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 950 ft18. Distance to nearest property line: 212 ft 19. Distance to nearest well permitted/completed in the same formation: 2164 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Raton	RTON	NA		NA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20040084

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
see attached

25. Distance to Nearest Mineral Lease Line: 402 ft 26. Total Acres in Lease: 1993

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Drilling pit

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	12+3/4	12+3/4	33.38	6			
SURF	11	8+5/8	24	1,000	210	1,000	0
1ST	7+7/8	5+1/2	15.5	2,325	344	2,325	0

32. BOP Equipment Type: ☐ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments The conductor will be hammered in. This is a refile, the location has moved slightly and the casing program has been modified, but the location is still in the same quarter/quarter and section. PDOP reading:13.2

34. Location ID: 333974

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Georgina Kovacik

Title: Engineering Tech Date: _____ Email: georgina.kovacik@pxd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER
05 071 09090 00

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400081376	30 DAY NOTICE LETTER	NOS_Wood_TR_T_2010.pdf
400081377	LEGAL/LEASE DESCRIPTION	LeaseDesc_Wood_R.pdf
400081386	SURFACE AGRMT/SURETY	SUEAgrmnt_Wood_2-31R.pdf
400081466	WELL LOCATION PLAT	WellPlat_Wood_31-2_R_rev.pdf

Total Attach: 4 Files