

Yuma County, Colorado

10—Colby silt loam, 3 to 6 percent slopes

Map Unit Setting

Elevation: 3,500 to 4,200 feet

Mean annual precipitation: 15 to 17 inches

Mean annual air temperature: 50 to 52 degrees F

Frost-free period: 130 to 150 days

Map Unit Composition

Colby and similar soils: 85 percent

Minor components: 15 percent

Description of Colby

Setting

Landform: Plains

Down-slope shape: Linear

Across-slope shape: Linear

Parent material: Loess

Properties and qualities

Slope: 3 to 6 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Well drained

*Capacity of the most limiting layer to transmit water
(Ksat):* Moderately high to high (0.57 to 2.00 in/hr)

Depth to water table: More than 80 inches

Frequency of flooding: None

Frequency of ponding: None

Calcium carbonate, maximum content: 15 percent

Available water capacity: High (about 10.2 inches)

Interpretive groups

Land capability classification (irrigated): 4e

Land capability (nonirrigated): 4e

Ecological site: Loamy Plains (R072XY001CO)

Typical profile

0 to 8 inches: Silt loam

8 to 60 inches: Silt loam

Minor Components

Keith

Percent of map unit: 8 percent

Kuma

Percent of map unit: 7 percent

Data Source Information

Soil Survey Area: Yuma County, Colorado
Survey Area Data: Version 13, Feb 23, 2010