

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400069917

Plugging Bond Surety

20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Howard Harris Phone: (303)606-4086 Fax: (303)629-8272

Email: Howard.Harris@Williams.com

7. Well Name: Farris Well Number: RWF 444-31

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8681

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 31 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.475105 Longitude: -107.929298

Footage at Surface: 330 FNL/FSL FSL FEL/FWL 2413 FWL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 5711 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 01/15/2010 PDOP Reading: 3.2 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 236 FSL 192 FEL 192 FEL 236 FSL 192 FEL 192
Sec: 31 Twp: 6S Rng: 94W Sec: 31 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 251 ft

18. Distance to nearest property line: 405 ft 19. Distance to nearest well permitted/completed in the same formation: 532 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-83	320	S/2 Fee Pooled

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached

25. Distance to Nearest Mineral Lease Line: 192 ft 26. Total Acres in Lease: 219

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-Use, Evap. & Backfill

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48	45	25	45	0
SURF	13+1/2	9+5/8	32.3	2,664	930	2,664	0
1ST	7+7/8	4+1/2	11.6	8,680	619	8,680	4,877

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Mud System Surface Use Agreement attached to form 2A Top of cement for production casing will be approx. 200 feet above top of Mesaverde.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Howard Harris

Title: Sr. Regulatory Specialist Date: 6/18/2010 Email: Howard.Harris@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/6/2010

API NUMBER

05 045 19781 00

Permit Number: _____ Expiration Date: 8/5/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)CEMENT TOP VERIFICATION BY CBL REQUIRED.

4)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 300 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400069917	FORM 2 SUBMITTED	LF@2492826 400069917
400070668	WELL LOCATION PLAT	LF@2492827 400070668
400070669	LEGAL/LEASE DESCRIPTION	LF@2492828 400070669
400070670	DEVIATED DRILLING PLAN	LF@2492829 400070670
400070671	DEVIATED DRILLING PLAN	LF@2492830 400070671

Total Attach: 5 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	PERMITITNG PASSED Changed commingle to no and added Related Forms information	8/4/2010 1:37:29 PM

Total: 1 comment(s)