



The SHL is 1,353' FNL & 493' FEL (SENE), Section 22, T12N, R67W, Weld County, CO. The state setback is 600' from the section lines.

**7" Casing:** 8-3/4" hole: KOP at 8,456'. Build curve at **12°/100'** to 90° inclination at 9,205' MD (**8,933' TVD**) at an azimuth of 278.45 ° and set 7" casing (1,283' FNL & 965' FEL, SENW, Section 22, T12N, R67W).

**North Lateral:** Drill a 6" horizontal well holding an azimuth of 278.45° to TD at a depth of 12,850' MD (**8,933' TVD**), 650' FNL & 650' FWL (NWNW) Section 22, T12N, R67W. Expect an inclination of 90.00°. Total 6" lateral is 3,645'.