

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400057815

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE ZONE COMMINGLE ZONE

Refiling

Sidetrack

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Susan Miller Phone: (303)228-4246 Fax: (303)228-4286

Email: smiller@nobleenergyinc.com

7. Well Name: LDS Well Number: D08-18D

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7564

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 5 Twp: 3N Rng: 64W Meridian: 6

Latitude: 40.247680 Longitude: -104.579350

Footage at Surface: 189 FNL/FSL FSL 1337 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4753 13. County: WELD

14. GPS Data:

Date of Measurement: 04/09/2010 PDOP Reading: 1.9 Instrument Operator's Name: Robert Daley

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL

1310 FNL 2550 FEL 1310 FNL 2550 FEL

Sec: 8 Twp: 3N Rng: 64W Sec: 8 Twp: 3N Rng: 64W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 175 ft

18. Distance to nearest property line: 189 ft 19. Distance to nearest well permitted/completed in the same formation: 843 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	407-87	160	GWA
Niobrara	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No Surface Owners Agreement Attached or \$25,000 Blanket Surface Bon \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T3N R64W: Section 8 All

25. Distance to Nearest Mineral Lease Line: 1310 ft 26. Total Acres in Lease: 938

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? Yes No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: Offsite Onsite
Method: Land Farming Land Spreading Disposal Facility Other: Closed loop

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	230	650	0
1ST	7+7/8	4+1/2	11.6	7,564	704	7,564	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments Conductor casing will not be used. 1st string top of cement will be 200' above the Niobrara formation. This well is part of a 4-well, multi-well pad permit. Production facilities will be located on the same location and dedicated to the well location being permitted. See Form 2A filed under LDS D08-29, document no. 400057777. Unit configuration: Section 8: W/2NE/4 and E/2NW/4. Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Waivers attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Susan Miller

Title: Regulatory Analyst II Date: 7/13/2010 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/13/2010

Permit Number: _____ Expiration Date: 8/12/2012

API NUMBER
05 123 31991 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

COGCC ENG COA - SME

- 1) Provide 24 hr notice of spud to Bo Brown at 970-330-6085 or email at bo.brown@state.co.us.
- 2) Set surface casing per Rule 317d, cement to surface. Setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.
- 3) If completed, provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below to 200' above Sussex. Verify coverage with cement bond log.
- 4) If dry hole, 40 sks cement 50' above Niobrara top, 40 sks cement 50' above Sussex top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. Restore surface location.
- 5) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

At the time of initial drilling of the well, the wellhead shall be located a distance of one hundred fifty (150) feet or one and one-half (1-1/2) times the height of the derrick, whichever is greater, from any building unit, public road, major above ground utility line, or railroad.

Attachment Check List

Att Doc Num	Name	Doc Description
400057815	FORM 2 SUBMITTED	LF@2506707 400057815
400066669	30 DAY NOTICE LETTER	LF@2506708 400066669
400066670	DEVIATED DRILLING PLAN	LF@2506709 400066670
400066671	EXCEPTION LOC WAIVERS	LF@2506710 400066671
400067556	WELL LOCATION PLAT	LF@2506711 400067556
400076307	EXCEPTION LOC REQUEST	LF@2506712 400076307
400076308	PROPOSED SPACING UNIT	LF@2506713 400076308
400076309	SURFACE AGRMT/SURETY	LF@2506714 400076309

Total Attach: 8 Files

Error: Subreport could not be shown.