

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400073863

Plugging Bond Surety

20030009

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: Susan Miller Phone: (303)228-4246 Fax: (303)228-4286

Email: smiller@nobleenergyinc.com

7. Well Name: STATE PC Well Number: AB16-02

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 9150

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 16 Twp: 7N Rng: 64W Meridian: 6

Latitude: 40.578690 Longitude: -104.551750

Footage at Surface: 610 FNL/FSL FNL FEL/FWL 1820 FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4880 13. County: WELD

14. GPS Data:

Date of Measurement: 06/15/2010 PDOP Reading: 2.7 Instrument Operator's Name: David C. Holmes

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1820 ft

18. Distance to nearest property line: 610 ft 19. Distance to nearest well permitted/completed in the same formation: 1285 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL	unspaced	80	W/2NE/4
Lyons	LYNS	unspaced	80	W/2NE/4
Niobrara	NBRR	unspaced	80	W/2NE/4

21. Mineral Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian Lease #: 8969.6

22. Surface Ownership: ☐ Fee ☒ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Sec 16 T7N R64W: All

25. Distance to Nearest Mineral Lease Line: 610 ft 26. Total Acres in Lease: 640

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	750	622	750	0
1ST	7+7/8	4+1/2	11.6	9,150	938	9,150	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. Production facilities will be located on the same location and dedicated to the location being permitted.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Susan Miller

Title: Regulatory Analyst II Date: 7/15/2010 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/13/2010

API NUMBER

05 123 31997 00

Permit Number: _____ Expiration Date: 8/12/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400073863	FORM 2 SUBMITTED	LF @ 2508563 400073863
400073966	30 DAY NOTICE LETTER	LF @ 2508564 400073966
400074215	WELL LOCATION PLAT	LF @ 2508565 400074215

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Engineer	<p>COGCC ENG COA - SME</p> <p>1) Provide 24 hr notice of spud to Ed Binkley at 970-302-1024 or e-mail at ed.binkley@state.co.us.</p> <p>2) Set surface casing, per Rule 317d, setting surface casing less than the approved depth is a permit violation unless prior written approval is obtained from the COGCC.</p> <p>3) If completed, cement coverage shall be at a minimum from the TD to 200' above Niobrara. Verify all placed cement with cement bond log and cementing tickets.</p> <p>4) If dry hole, set 40 sks cement 50' above Lyons top, 115 sks cement from 50' below J Sand base to 50' above D Sand top, 40 sks cement 50' above Niobrara top, 50 sks cement ½ out, ½ in surface casing, 10 sks cement top of surface casing, cut 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole. Restore surface location.</p>	8/8/2010 6:07:35 PM

Total: 1 comment(s)

Error: Subreport could not be shown.