

FORM

2

Rev  
12/05

## State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400078829

Plugging Bond Surety

20090040

## APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
 SINGLE ZONE ☐ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐
Refiling ☒Sidetrack ☐3. Name of Operator: FRAM OPERATING LLC4. COGCC Operator Number: 103105. Address: 30 E PIKES PEAK AVE STE 283City: COLORADO State: CO Zip: 80903  
SPRINGS6. Contact Name: David Cook Phone: (719)593-8787 Fax: (713)314-1362Email: dave@framamericas.com7. Well Name: Whiting Well Number: 35-38. Unit Name (if appl): Whitewater Unit Number: 73038X9. Proposed Total Measured Depth: 2900

## WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 35 Twp: 2S Rng: 2E Meridian: ULatitude: 38.937300 Longitude: -108.336420
 Footage at Surface: 1708 FNL/FSL FSL 1982 FEL/FWL FEL
11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 5318 13. County: MESA

## 14. GPS Data:

Date of Measurement: 07/13/2005 PDOP Reading: 6.0 Instrument Operator's Name: Jeff Fletcher15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

 \_\_\_\_\_  
 Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 300 ft18. Distance to nearest property line: 680 ft 19. Distance to nearest well permitted/completed in the same formation: 9240 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Dakota	DKTA			
Entrada	ENRD			
Morrison	MRSN			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
See attached Lease Property Description.

25. Distance to Nearest Mineral Lease Line: 680 ft 26. Total Acres in Lease: 1648

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No **If 28, 29, or 30 are "Yes" a pit permit may be required.**

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: Will use closed loop system

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	20	16	24#	40	100	40	
SURF	13+3/8	9+5/8	36#	400	125	400	
2ND	8+1/2	5+1/2	15.5#	2,900	230	400	1,400

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments The pad is built, pits constructed, this refile will not require any expansion/additional surface disturbance, the location does not require a variance of the rules listed in 306.d.(1).(A).(ii) and the location is not in a wildlife restricted occupance area. 30-day notice letter mailed 7/9/10.

34. Location ID: 312717

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☐ Yes ☒ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: David Cook

Title: Manager Date: 8/9/2010 Email: dave@framamericas.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**API NUMBER**

05 077 08941 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400078829	FORM 2 SUBMITTED	400078829.pdf
400084595	LEGAL/LEASE DESCRIPTION	Legal Description.pdf
400084597	30 DAY NOTICE LETTER	30-day notice letter, 306 consult & 318b waiver.pdf

Total Attach: 3 Files