

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

 OIL ☐ GAS ☒ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

 Refiling ☐
 Sidetrack ☐

Document Number:

400080289

Plugging Bond Surety

20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Kelly Huffman Phone: (303)831-3974 Fax: (303)860-5838

Email: khuffman@petd.com

7. Well Name: Coors Energy Well Number: 33-25D

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 7094

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 25 Twp: 3N Rng: 64W Meridian: 6

Latitude: 40.191150 Longitude: -104.495280

 Footage at Surface: 726 FSL 1376 FEL
 FNL/FSL FEL/FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4790 13. County: WELD

14. GPS Data:

Date of Measurement: 02/17/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G. Carlson

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.
 Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
 1984 FSL 1976 FEL 1984 FSL 1976 FEL
 Sec: 25 Twp: 3N Rng: 64W Sec: 25 Twp: 3N Rng: 64W
16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1118 ft

18. Distance to nearest property line: 726 ft 19. Distance to nearest well permitted/completed in the same formation: 815 ft

20.

LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Dakota	DKTA	499-15	320	E/2
J-Sand	JSND	232-23	320	E/2
Niobrara Codell	NB-CD	407-87	80	N/2SE/4
Sussex Shannon	SX-SN	N/A	80	N/2SE/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
Township 3 North, Range 64 West, 6th P.M. Section 25: NE/4NE/4, NW/4NW/4, SE/4NW/4, S/2 (and lands in other sections)

25. Distance to Nearest Mineral Lease Line: 726 ft 26. Total Acres in Lease: 2889

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	700	500	700	0
1ST	7+7/8	4+1/2	10.5	7,094	120	7,094	6,594
			Stage Tool	6,594	525	6,594	0

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. The Coors Energy 25D, 33-25D, 43-25D, 25XD, 44-25D, 25YD and 25TD wells will be drilled from the same pad. The wells will be tied into a tank battery facility located approximately 260' SSE of the well site.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Kelly Huffman

Title: Contract Land Tech Date: _____ Email: khuffman@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Permit Number: _____ Expiration Date: _____

API NUMBER

05

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Attachment Check List

Att Doc Num	Name	Doc Description
400080296	EXCEPTION LOC WAIVERS	Coors Energy 25 SWSE SLW.pdf
400080297	PLAT	Coors Energy 33-25D - Plat - 2-17-10.pdf
400080298	DEVIATED DRILLING PLAN	Coors Energy 33-25D Deviated Drilling Plan.pdf
400080299	30 DAY NOTICE LETTER	Coors Energy S2 305e Land Owner Notice 2-24-10.pdf
400080445	EXCEPTION LOC REQUEST	Coors Energy 25-SWSE SLW Letter to Director.pdf
400082044	TOPO MAP	Coors Energy 33-25D Topo.pdf

Total Attach: 6 Files