

**Map Unit Description**

Weld County, Colorado, Southern Part

**69 Valent sand, 0 to 3 percent slopes**

**Setting**

Elevation: 4650 to 5100 feet  
Mean annual precipitation: 13 to 19 inches  
Mean annual air temperature: 48 to 52 degrees F  
Frost-free period: 130 to 180 days

**Composition**

Valent and similar soils: 90 percent  
Minor components: 10 percent

**Description of Valent**

**Setting**

Landform: Plains  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Eolian deposits

**Properties and Qualities**

Slope: 0 to 3 percent  
Drainage class: Excessively drained  
Capacity of the most limiting layer to transmit water (Ksat): High or very high (5.95 to 19.98 in/hr)  
Frequency of flooding: None  
Frequency of ponding: None  
Calcium carbonate maximum: 0 percent  
Gypsum maximum: 0 percent  
Available water capacity: Very low (about 2.6 inches)

**Interpretive Groups**

Land capability classification (irrigated): 4e  
Land capability (non irrigated): 6e  
Ecological site: Deep Sand (R067BY015CO)

**Typical Profile**

0 to 8 inches: fine sand  
8 to 60 inches: sand

**Minor Components**

**Osgood**

Percent of map unit: 10 percent