



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

198227

Date 7/9/2010	Well Owner KERR/McGEE	Well No. 29-36	Lease BERNHARDT
County WELD	State COLORADO	Field	
Charge to KERR/McGEE OIL & GAS ONSHORE, LP	Charge Code		For Office Use Only
Address 999 BROADWAY, STE 3700 (XTREME #11)			
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No. 1216/1214	Code
Type of Job	Depth	Ft. 895	To
Surface 8 3/8" CSG-24 #	Bottom of Surface	Ft. 880	To
Plug	Plug Landed @ 836	Ft.	Time On 1530
Production	Pipe Landed @ 880	Ft.	Time Off PLUG Down 1745

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat TYPE III	550	SKS		
	Poz. Mix		WHITE LIME GREEN		
	Calcium Chloride	2.5%	User ID 20016		
	Gel % Flo-Cele 1/4 #Per Sack		WATER/CEMENT 2036274		
	Handling Charge		GA. Acol.	800/2090	210
	Hauling Charge				
	Additional Cement				
	MIXING RATE 4BPM		PRE-FLUSH 1703-1709		
	DISP. RATE 5BPM		MIX 1709-1731		
	SLURRY VOL 1.32 FT/SK		CHANGE VALVES 1731-1734		
	SLURRY WT 14.8-15 PPG		DISPLACE 1734-1745		
	WATER/TEMP 66		LANDED PLUG @ 500 PSI		
	WATER/CEMENT 6.25 GALS/SK		TOTAL SLURRY VOL 129 BBLS CEMENT		
			FINAL LIFT 475		

Remarks PRE-FLUSH W/30 BBLS H₂O	Tax Reference Code	Sub Total
DISPLACE W/53 BBLS H₂O	State 2.9 %	Tax
CIRCULATE 6 BBLS CEMENT	Disc.	Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		23			
1216/1214		Bulk Truck		2123			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jam/OSCAR DALLAS**

Received By

Customer or His Agent