

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

2583285

Plugging Bond Surety

20090080

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

3. Name of Operator: GREAT WESTERN OIL & GAS COMPANY LLC

4. COGCC Operator Number: 10110

5. Address: 503 MAIN ST

City: WINDSOR State: CO Zip: 80550

6. Contact Name: JEFF REALE Phone: (970)686-8831 Fax: (866)413-3354

Email: JREALE@GWOGCO.COM

7. Well Name: GUSTAFSON Well Number: 31-52

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7500

WELL LOCATION INFORMATION

10. QtrQtr: NENW Sec: 31 Twp: 7N Rng: 65W Meridian: 6

Latitude: 40.535450 Longitude: -104.710390

Footage at Surface: 1313 FNL/FSL FNL 1517 FEL/FWL FWL

11. Field Name: EATON Field Number: 19350

12. Ground Elevation: 4825 13. County: WELD

14. GPS Data:

Date of Measurement: 12/21/2007 PDOP Reading: 2.1 Instrument Operator's Name: E. HERNANDEZ

15. If well is ☐ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL _____ FEL/FWL _____ Bottom Hole: FNL/FSL _____ FEL/FWL _____

Sec: _____ Twp: _____ Rng: _____ Sec: _____ Twp: _____ Rng: _____

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 710 ft

18. Distance to nearest property line: 700 ft 19. Distance to nearest well permitted/completed in the same formation: 871 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA-CODELL	NB-CD		160	NW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
FOR DESCRIPTION OF PLAT, REFERENCE EXHIBIT A- MINERAL LEASE MAP ATTACHED.

25. Distance to Nearest Mineral Lease Line: 700 ft 26. Total Acres in Lease: 105

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	520	300	520	0
1ST	7+7/8	4+1/2	11.6	7,450	300	7,450	6,350

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments CONDUCTOR CASING WILL NOT BE SET. 30-DAY WAIVER IN SUA. NO CHANGES OR IMPROVEMENTS HAVE BEEN MADE WITHIN 500 FT. OF THE PROPOSED WELLHEAD LOCATION IN THE PAST YEAR.

34. Location ID: 309905

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JEFF REALE

Title: VP OPERATIONS Date: 7/22/2010 Email: JREALE@GWOGCO.COM

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/18/2010

API NUMBER

05 123 25565 00

Permit Number: _____ Expiration Date: 8/17/2012

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.

Attachment Check List

Att Doc Num	Name	Doc Description
2583285	APD ORIGINAL	LF@2512020 2583285
2583286	WELL LOCATION PLAT	LF@2512021 2583286
2583287	TOPO MAP	LF@2512022 2583287
2583288	MINERAL LEASE MAP	LF@2512023 2583288

Total Attach: 4 Files

Error: Subreport could not be shown.