

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refiling ☒

Sidetrack ☐

Document Number:

400058964

Plugging Bond Surety

20040105

3. Name of Operator: BERRY PETROLEUM COMPANY

4. COGCC Operator Number: 10091

5. Address: 1999 BROADWAY STE 3700

City: DENVER State: CO Zip: 80202

6. Contact Name: JANNI KEIDEL Phone: (303)999-4225 Fax: (303)999-4325

Email: jek@bry.com

7. Well Name: MILK CABIN OM Well Number: 14D M32 595

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11414

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 32 Twp: 5S Rng: 95W Meridian: 6

Latitude: 39.564422 Longitude: -108.082883

Footage at Surface: 498 FNL/FSL FSL 1257 FEL/FWL FWL

11. Field Name: PARACHUTE Field Number: 67350

12. Ground Elevation: 8121 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/31/2006 PDOP Reading: 1.7 Instrument Operator's Name: ROBERT KAY

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 411 FSL 2148 FEL/FWL FWL Bottom Hole: FNL/FSL 411 FSL 2148 FEL/FWL FWL
Sec: 32 Twp: 5S Rng: 95W Sec: 32 Twp: 5S Rng: 95W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 7920 ft

18. Distance to nearest property line: 6468 ft 19. Distance to nearest well permitted/completed in the same formation: 645 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
WILLIAMS FORK	WMFK	510-13		SWSW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
PLEASE SEE MINERAL LEASE MAP ATTACHED TO ORIGINAL APD.

25. Distance to Nearest Mineral Lease Line: 5625 ft 26. Total Acres in Lease: 25000

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	30	20	55	90	100	90	0
SURF	16	9+5/8	36	2,500	1,000	2,500	0
3RD	8+3/4	4+1/2	11.6	11,414	600	11,414	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments I certify that there have been no changes on land use, lease description. Pad has been built. Pit has been constructed. Wells have not been drilled. Conductors have not been set. No rig on site. The refile will not require any expansion / additional surface disturbance of pad. The location does not require a variance from any of the rules listed in Rule 306.d. (1). (A). (ii). The location is not in a restricted surface occupancy area. The location is not in a sensitive wildlife habitat area. The production casing Top of Cement will be 200' above the Top of Gas. Berry Petroleum Company will be doing closed loop operations.

34. Location ID: 335868

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JANNI KEIDEL

Title: PERMITTING AGENT Date: 6/29/2010 Email: jek@bry.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 8/4/2010

Permit Number: _____ Expiration Date: 8/3/2012

API NUMBER

05 045 13261 00

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- 2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE
- 3) CEMENT TOP VERIFICATION BY CBL REQUIRED.
- 4) COMPLY WITH ALL PROVISIONS OF THE JUNE 12, 2008 NOTICE TO OPERATORS DRILLING WELLS WITHIN 3/4 MILE OF THE RIM OF THE ROAN PLATEAU IN GARFIELD COUNTY - PIT DESIGN, CONSTRUCTION AND MONITORING REQUIREMENTS. SEE ATTACHED NOTICE.
- 5) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
400058964	APD APPROVED	400058964.pdf
400072299	WELL LOCATION PLAT	LF@2499898 400072299
400072300	MINERAL LEASE MAP	LF@2499899 400072300
400072308	ACCESS ROAD MAP	LF@2499900 400072308
400073068	DEVIATED DRILLING PLAN	LF@2499901 400073068
400073639	30 DAY NOTICE LETTER	LF@2499902 400073639
400082390	FORM 2 SUBMITTED	LF@2499897 400082390

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	PERMITTING PASSED. Removed surface bond # per JK. 08/03/10 plg.	8/3/2010 11:21:51 AM

Total: 1 comment(s)

Error: Subreport could not be shown.