

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐
Sidetrack ☐

Document Number:

400066796

Plugging Bond Surety

20010023

3. Name of Operator: K P KAUFFMAN COMPANY INC

4. COGCC Operator Number: 46290

5. Address: 1675 BROADWAY, STE 2800

City: DENVER State: CO Zip: 80202

6. Contact Name: Sherry Glass Phone: (303)825-4822 Fax: (303)825-4825
Email: sglass@kpk.com

7. Well Name: Anderson Well Number: #14-32-19

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8143

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 32 Twp: 4N Rng: 67W Meridian: 6

Latitude: 40.264380 Longitude: -104.915910

Footage at Surface: 696 FNL/FSL FSL 2068 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4948 13. County: WELD

14. GPS Data:

Date of Measurement: 01/30/2009 PDOP Reading: 6.0 Instrument Operator's Name: Kipper Goldsberry

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1320 FSL 1320 FEL/FWL 1320 FEL/FWL 1320
Bottom Hole: FNL/FSL 1320 FSL 1320 FEL/FWL 1320 FEL/FWL 1320
Sec: 32 Twp: 4N Rng: 67W Sec: 32 Twp: 4N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 544 ft

18. Distance to nearest property line: 482 ft 19. Distance to nearest well permitted/completed in the same formation: 863 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-Sand	JSND	232-23	320	W/2
Niobrara-Codell	NB-CD	407-87	160	SW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010024

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SW/4 section 32-T4N-R67W

25. Distance to Nearest Mineral Lease Line: 1320 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24#	700	450	700	
1ST	7+7/8	4+1/2	11.5#	8,143	700	8,143	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments There will be no conductor pipe used in this well.

34. Location ID: 332641

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sherry Glass

Title: Engineering Technician Date: 6/11/2010 Email: sglass@kpk.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/4/2010

API NUMBER

05 123 31953 00

Permit Number: _____ Expiration Date: 8/3/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

- 1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Run and submit Directional Survey from TD to base of surface casing. The operator shall comply with Rule 321, and it shall be the operator's responsibility to ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
400066796	APD APPROVED	400066796.pdf
400067070	LEASE MAP	LF@2490388 400067070
400067071	PLAT	LF@2490389 400067071
400067073	TOPO MAP	LF@2490390 400067073
400067076	30 DAY NOTICE LETTER	LF@2490391 400067076
400068557	DEVIATED DRILLING PLAN	LF@2490392 400068557
400082381	FORM 2 SUBMITTED	LF@2490387 400082381

Total Attach: 7 Files

Error: Subreport could not be shown.