

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐  
Sidetrack ☐

Document Number:

400069185

Plugging Bond Surety

20090078

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Kelly Huffman Phone: (303)831-3974 Fax: (303)860-5838  
Email: khuffman@petd.com

7. Well Name: Spaur Well Number: 10GD

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7611

WELL LOCATION INFORMATION

10. QtrQtr: NWSW Sec: 10 Twp: 4N Rng: 67W Meridian: 6

Latitude: 40.324680 Longitude: -104.884720

Footage at Surface: 1809 FNL/FSL FSL 521 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4805 13. County: WELD

14. GPS Data:

Date of Measurement: 05/18/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G. Carlson

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 2618 FSL 50 FWL FWL Bottom Hole: FNL/FSL 2618 FSL 50 FWL FWL  
Sec: 10 Twp: 4N Rng: 67W Sec: 10 Twp: 4N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 562 ft

18. Distance to nearest property line: 157 ft 19. Distance to nearest well permitted/completed in the same formation: 871 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara Codell	NB-CD	407-87	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
Township 4 North, Range 67 West, 6th P.M. Section 10: SW/4

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 160

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	12+1/4	8+5/8	24	650	390	650	0
1ST	7+7/8	4+1/2	10.5	7,611	212	7,611	6,211
S.C. 1.1	7+7/8	4+1/2	10.5	7,611	212	7,611	6,211

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. The Spaur 10GD will be drilled from the same pad as the Spaur 10HD and 23-10D wells. The well will be tied into the tank battery facility located approximately 412' to the west of the well site which currently services the Spaur 10-1 well. Proposed GWA spacing unit: Sec 9: SENE & NESE ; Sec 10: SWNW & NWSW (160) Petroleum Development Corporation requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location.

34. Location ID: 323182

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kelly Huffman

Title: Contract Land Tech Date: 7/12/2010 Email: khuffman@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 8/4/2010

Permit Number: \_\_\_\_\_ Expiration Date: 8/3/2012

**API NUMBER**

05 123 31954 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Operator must meet water well testing requirements as per Rule 318A.e.(4).

1) Provide 24 hour notice of MIRU to Bo Brown at 970-397-4124 or e-mail at bo.brown@state.co.us.

2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.

3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

**Attachment Check List**

Att Doc Num	Name	Doc Description
400069185	APD APPROVED	400069185.pdf
400069191	PLAT	LF@2505868 400069191
400069192	TOPO MAP	LF@2505869 400069192
400069193	30 DAY NOTICE LETTER	LF@2505870 400069193
400069194	EXCEPTION LOC WAIVERS	LF@2505871 400069194
400074718	DEVIATED DRILLING PLAN	LF@2505872 400074718
400074719	PROPOSED SPACING UNIT	LF@2505873 400074719
400074720	PROPOSED SPACING UNIT	LF@2505874 400074720
400074721	EXCEPTION LOC REQUEST	LF@2505875 400074721
400082399	FORM 2 SUBMITTED	LF@2505867 400082399

Total Attach: 10 Files

Error: Subreport could not be shown.