

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



|    |    |    |    |
|----|----|----|----|
| DE | ET | OE | ES |
|----|----|----|----|

Document Number:

400071800

Plugging Bond Surety

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240  
Email: Julia.Carter@encana.com

7. Well Name: SGU Well Number: 8503B-25 F25496

8. Unit Name (if appl): Big Jimmy Unit Unit Number: COC74105X

9. Proposed Total Measured Depth: 13980

WELL LOCATION INFORMATION

10. QtrQtr: SENE Sec: 25 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.674342 Longitude: -108.119581

Footage at Surface: 2267 FNL/FSL FNL 1958 FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 8298 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/07/2009 PDOP Reading: 1.7 Instrument Operator's Name: Robert Kay

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 430 FNL 1931 FWL 430 FNL 1931 FWL  
Sec: 25 Twp: 4S Rng: 96W Sec: 25 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 409 ft

18. Distance to nearest property line: 1958 ft 19. Distance to nearest well permitted/completed in the same formation: 400 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Iles                   | ILES           |                         |                               |                                      |
| Williams Fork          | WMFK           | 510-13                  | 10                            |                                      |

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC61136

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T4S, R96W, Section 25: ALL

25. Distance to Nearest Mineral Lease Line: 430 ft 26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle, Amend and Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Weight Per Foot | Setting Depth | Sacks Cement | Cement Bottom | Cement Top |
|-------------|--------------|----------------|-----------------|---------------|--------------|---------------|------------|
| CONDUCTOR   | 26           | 20             | Line Pipe       | 120           | 176          | 120           | 0          |
| SURF        | 14+3/4       | 9+5/8          | 36              | 3,000         | 1,047        | 3,000         | 0          |
| 1ST         | 7+7/8        | 4+1/2          | 11.6            | 13,980        | 645          | 13,980        | 8,320      |

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana Oil & Gas (USA) Inc. owns surface. Please note cement will be run to surface for both conductor and surface casing. The surface casing hole size will be 14-3/4", 12-1/4" or 13-1/2". Production casing hole size will be both 7-7/8" and 8-3/4". Production cement top calculation 500' above TOG. Onsite was on 8/12/2009 with BLM and CDOW. Plugging Bond ID removed w/permission of operator. SF 6/28/10

34. Location ID: 415182

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 6/25/2010 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/4/2010

API NUMBER

05 045 19762 00

Permit Number: \_\_\_\_\_ Expiration Date: 8/3/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) CEMENT TOP VERIFICATION BY CBL REQUIRED.

4) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

| Att Doc Num | Name                   | Doc Description      |
|-------------|------------------------|----------------------|
| 400071800   | APD APPROVED           | 400071800.pdf        |
| 400071810   | PLAT                   | LF@2498220 400071810 |
| 400071811   | DEVIATED DRILLING PLAN | LF@2498221 400071811 |
| 400071816   | MINERAL LEASE MAP      | LF@2498222 400071816 |
| 400071818   | TOPO MAP               | LF@2498223 400071818 |
| 400072905   | FED. DRILLING PERMIT   | LF@2498224 400072905 |
| 400082435   | FORM 2 SUBMITTED       | LF@2498219 400082435 |

Total Attach: 7 Files

Error: Subreport could not be shown.