

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ZONE ☐ COMMINGLE ZONE ☐

Refilling ☐
Sidetrack ☐

Document Number:

400070198

Plugging Bond Surety

20030107

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY

4. COGCC Operator Number: 96850

5. Address: 1515 ARAPAHOE ST STE 1000

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8272

Email: Greg.J.Davis@Williams.com

7. Well Name: Savage Well Number: RWF 322-34

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8341

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 27 Twp: 6S Rng: 94W Meridian: 6

Latitude: 39.490145 Longitude: -107.872533

Footage at Surface: 423 FNL/FSL FSL 2186 FEL/FWL FEL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 5297 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 11/06/2008 PDOP Reading: 1.5 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FNL/FSL Bottom Hole: FNL/FSL FNL/FSL
1988 FNL 2106 FWL 1988 FNL 2106 FWL
Sec: 34 Twp: 6S Rng: 94W Sec: 34 Twp: 6S Rng: 94W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 842 ft

18. Distance to nearest property line: 498 ft 19. Distance to nearest well permitted/completed in the same formation: 825

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-66	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
See Attached

25. Distance to Nearest Mineral Lease Line: 789 ft 26. Total Acres in Lease: 1476

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
CONDUCTOR	24	18	48#	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	1,756	597	1,756	0
1ST	7+7/8	4+1/2	11.6#	8,341	710	8,341	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Loop. Cement 200' OR MORE above uppermost mvrd sand. CA COC60596

34. Location ID: 323938

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 7/8/2010 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/25/2010

API NUMBER

05 045 19833 00

Permit Number: _____ Expiration Date: 8/24/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- (1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- (2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.
- (3) RESERVE PIT MUST BE LINED.
- (4) CEMENT-TOP VERIFICATION BY CBL REQUIRED.
- (5) OPERATOR MUST ENSURE 110 PERCENT SECONDARY CONTAINMENT FOR ANY VOLUME OF FLUIDS CONTAINED AT WELL-SITE DURING DRILLING AND COMPLETION OPERATIONS. IF FLUIDS ARE CONVEYED VIA PIPELINE, OPERATOR MUST IMPLEMENT BEST-MANAGEMENT-PRACTICES TO CONTAIN ANY UNINTENTIONAL RELEASE OF FLUIDS.
- (6) FLOWBACK TO TANKS ONLY. SUBMIT A SECONDARY AND TERTIARY CONTAINMENT PLAN VIA SUNDRY NOTICE FORM 4 FOR THE TANKS. ATTN: CHRIS CANFIELD. OBTAIN APPROVAL OF THE PLAN PRIOR TO FLOWBACK.
- (7) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.
- (8) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 250 FEET DEEP.

Attachment Check List

Att Doc Num	Name	Doc Description
2089299	LEGAL/LEASE DESCRIPTION	LF@2526841 2089299
400070198	FORM 2 SUBMITTED	LF@2504347 400070198
400074962	WELL LOCATION PLAT	LF@2504348 400074962
400074963	LEGAL/LEASE DESCRIPTION	LF@2504349 400074963
400074964	SURFACE AGRMT/SURETY	LF@2504350 400074964
400074965	TOPO MAP	LF@2504351 400074965
400074995	DEVIATED DRILLING PLAN	LF@2504353 400074995

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	PERMITTING PASSED Received lease from Greg Davis and imported into eForm	8/20/2010 11:08:38 AM
Permit	Changed commingle to no per verbal from Greg Davis Lease appears to be only for shallow rights, Greg Davis is checking leasing information	8/19/2010 11:45:13 AM

Total: 2 comment(s)

Error: Subreport could not be shown.