



TECHNICAL INFORMATION PAGE



FOR OGCC USE ONLY

RECEIVED

AUG 20 2010

COGCC/Rifle Office

1. OGCC Operator Number: 27742 API Number: 05-057-06480-00
2. Name of Operator: EOG Resources, Inc. OGCC Facility ID #
3. Well/Facility Name: Surprise Well/Facility Number: 4-06H
4. Location (QtrQtr, Sec, Twp, Rng, Meridian): SWSE, Section 6, T6N, R80W, 6th Meridian

This form is to be completed whenever a Sundry Notice is submitted requiring detailed report of work to be performed or completed. This form shall be transmitted within 30 days of work completed as a "subsequent" report and must accompany Form 4, page 1.

5.

**DESCRIBE PROPOSED OR COMPLETED OPERATIONS**

EOG Resources, Inc. (EOG) requests permission to use swell packers as an option for isolation of productive intervals on the 4 ½" liner in lieu of cementing the liner in place on the Surprise 4-06H well as originally permitted.

The decision to utilize swell packers instead of cementing the production liner in place will be based on hole conditions encountered and an openhole caliper log run in the lateral at the conclusion of drilling. In the event it appears from analysis of this information on location at the time that completion of the lateral could be more fully optimized by running swell packers, EOG would opt for this procedure. Should hole conditions not appear favorable for the swell packer option, the 4 ½" production liner would be cemented in place as originally planned. All other permitted procedures for the Surprise 4-06H would remain unchanged, including the location of the top of the producing zone (intermediate casing point) at 616' FNL and 2016' FWL of Section 7, T6N, R80W and the intermediate casing cement program to insure its integrity.