

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400079049

Plugging Bond Surety

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: CHERYL LIGHT Phone: (720)929-6461 Fax: (720)929-7461

Email: CHERYL.LIGHT@ANADARKO.COM

7. Well Name: BADDING Well Number: 23-35

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8122

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 35 Twp: 2N Rng: 66W Meridian: 6

Latitude: 40.090107 Longitude: -104.747845

Footage at Surface: 1017 FNL/FSL FSL 1647 FEL/FWL FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 5107 13. County: WELD

14. GPS Data:

Date of Measurement: 04/27/2010 PDOP Reading: 1.9 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1335 FSL 2590 FEL FEL Bottom Hole: FNL/FSL 1335 FSL 2590 FEL FEL
Sec: 35 Twp: 2N Rng: 66W Sec: 35 Twp: 2N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1017 ft

18. Distance to nearest property line: 1017 ft 19. Distance to nearest well permitted/completed in the same formation: 1089 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J-SAND	JSND	232	320	GWA
NIOBRARA-CODELL	NB-CD	407	160	GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20010125

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bon ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
SEE ATTACHED OIL & GAS LEASE

25. Distance to Nearest Mineral Lease Line: 50 ft 26. Total Acres in Lease: 5737

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☒ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	1,140	777	1,140	0
1ST	7+7/8	4+1/2	11.6	8,122	200	8,122	
1ST LINER							

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED. PROPOSED GWA UNIT CONFIGURATION FOR NB-CD: E/2SW & W/2SE PROPOSED GWA UNIT CONFIGURATION FOR J-SAND: S/2

34. Location ID: 319409

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CHERYL LIGHT

Title: SR. REGULATORY ANALYST Date: 7/28/2010 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 8/26/2010

API NUMBER

05 123 32082 00

Permit Number: _____ Expiration Date: 8/25/2012

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Note surface casing setting depth change from 1110' to 1140'. Increase cement coverage accordingly and cement to surface.
- 2) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 3) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Sussex. Verify coverage with cement bond log.
- 4) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name	Doc Description
400079049	FORM 2 SUBMITTED	LF@2514904 400079049
400079051	WELL LOCATION PLAT	LF@2514905 400079051
400079052	TOPO MAP	LF@2514906 400079052
400079053	OIL & GAS LEASE	LF@2514907 400079053
400079054	30 DAY NOTICE LETTER	LF@2514908 400079054
400079055	DEVIATED DRILLING PLAN	LF@2514909 400079055
400079056	PROPOSED SPACING UNIT	LF@2514910 400079056
400079057	MULTI-WELL PLAN	LF@2514911 400079057

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Per Cheryl Light, change J-Sand unit acreage from 160 to 320 and change unit configuration from (E/2SW & W/2SE) to S/2, and enter 232 as J-Sand spacing order.	8/25/2010 7:34:47 AM
Permit	J-SAND unit configuration must conform to the existing unit, S/2 (320). Requested to change unit acreage from 160 to 320 and the unit configuration from (E2SW & W2SE) to S/2. PVG	8/20/2010 12:35:15 PM

Total: 2 comment(s)

Error: Subreport could not be shown.