

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400071921

Plugging Bond Surety

20090078

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ZONE ☒ COMMINGLE ZONE ☒

Refiling ☐

Sidetrack ☐

3. Name of Operator: PETROLEUM DEVELOPMENT CORPORATION

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Kelly Huffman Phone: (303)831-3974 Fax: (303)860-5838

Email: khuffman@petd.com

7. Well Name: Carlson Well Number: 23-2D

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 7566

WELL LOCATION INFORMATION

10. QtrQtr: NESW Sec: 2 Twp: 6N Rng: 66W Meridian: 6

Latitude: 40.516010 Longitude: -104.745520

Footage at Surface: 2136 FNL/FSL FSL 2571 FEL/FWL FWL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4860 13. County: WELD

14. GPS Data:

Date of Measurement: 06/16/2010 PDOP Reading: 6.0 Instrument Operator's Name: Thomas G. Carlson

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 1973 FSL FSL 2000 FWL FWL Bottom Hole: FNL/FSL 1973 FSL FSL 2000 FWL FWL  
Sec: 2 Twp: 6N Rng: 66W Sec: 2 Twp: 6N Rng: 66W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2000 ft

18. Distance to nearest property line: 107 ft 19. Distance to nearest well permitted/completed in the same formation: 642 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara Codell	NB-CD	407-87	80	E/2SW/4
Sussex Shannon	SX-SN	n/a	80	E/2SW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
 Township 6 North, Range 66 West, 6th P.M. Section 2: SW/4, except Lot A of Recorded Exemption No. 0805-2-3-RE-1502 and except Lot A of Recorded Exemption No. 0805-02-3-re-3813; Township 6 North, Range 66 West, 6th P.M. Section 2: That part of the S/2SW/4 described as Lot A of Recorded Exemption No. 0805-2-3-RE-1502

25. Distance to Nearest Mineral Lease Line: 115 ft 26. Total Acres in Lease: 158

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 27 or 28 are yes, is this location in a sensitive area (Rule 903)? ☐ Yes ☐ No If 28, 29, or 30 are "Yes" a pit permit may be required.

31. Mud disposal: ☐ Offsite ☒ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24	650	390	650	0
1ST	7+7/8	4+1/2	10.5	7,566	204	7,566	6,166

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. The Carlson 23-2D will be drilled from the same pad as the Carlson 2PD, 2BD, 13-2D, 2KD, 2OD and Leffler 2SD. The well will be tied into a tank battery facility located near the pad site. Petroleum Development Corporation requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Petroleum Development Corporation requests approval of a Rule 603.a.(2) exception location: Wellhead is to be located less than 150' from a property line.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Kelly Huffman

Title: Contract Land Tech Date: 6/23/2010 Email: khuffman@petd.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nash Director of COGCC Date: 8/27/2010

Permit Number: \_\_\_\_\_ Expiration Date: 8/26/2012

**API NUMBER**

05 123 32122 00

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Ed Binkley at 970-506-9834 or e-mail at ed.binkley@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

**Attachment Check List**

Att Doc Num	Name	Doc Description
2621848	WELL LOCATION PLAT	LF@2530870 2621848
2621849	DEVIATED DRILLING PLAN	LF@2530871 2621849
2621850	EXCEPTION LOC REQUEST	LF@2530872 2621850
2621851	EXCEPTION LOC WAIVERS	LF@2530874 2621851
2621852	EXCEPTION LOC REQUEST	LF@2530875 2621852
2621853	EXCEPTION LOC WAIVERS	LF@2530878 2621853
400071921	FORM 2 SUBMITTED	LF@2496516 400071921
400071926	TOPO MAP	LF@2496518 400071926
400071927	30 DAY NOTICE LETTER	LF@2496519 400071927

Total Attach: 9 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Uploaded new property line exception location waiver and request, new Aa & Ac exception location waiver and request, new deviated drilling plan, and new well location plat to application as attachments. Deleted old copies of the same documents. PVG	8/26/2010 3:35:58 PM

Total: 1 comment(s)

Error: Subreport could not be shown.