

## Map Unit Description

Fremont County Area, Colorado

### 52 Kim-Cascajo complex, 2 to 15 percent slopes

#### Setting

Elevation: 5000 to 6000 feet  
Mean annual precipitation: 10 to 13 inches  
Mean annual air temperature: 49 to 53 degrees F  
Frost-free period: 125 to 165 days

#### Composition

Kim and similar soils: 50 percent  
Cascajo and similar soils: 35 percent

#### Description of Kim

##### Setting

Landform: Fan terraces, stream terraces, fans  
Down-slope shape: Linear  
Across-slope shape: Linear  
Parent material: Sandy and gravelly alluvium

##### Properties and Qualities

Slope: 2 to 10 percent  
Drainage class: Well drained  
Capacity of the most limiting layer to transmit water (Ksat): Moderately high or high (0.60 to 2.00 in/hr)  
Frequency of flooding: None  
Frequency of ponding: None  
Calcium carbonate maximum: 15 percent  
Gypsum maximum: 0 percent  
Available water capacity: High (about 10.1 inches)

##### Interpretive Groups

Land capability (non irrigated): 6c  
Ecological site: Loamy Plains (R069XY006CO)

##### Typical Profile

0 to 4 inches: loam  
4 to 60 inches: loam, clay loam, sandy clay loam

#### Description of Cascajo

##### Setting

Landform: Fan terraces, fans, stream terraces  
Down-slope shape: Linear  
Across-slope shape: Linear

##### Properties and Qualities

Slope: 10 to 15 percent  
Drainage class: Excessively drained  
Capacity of the most limiting layer to transmit water (Ksat): High (2.00 to 6.00 in/hr)  
Frequency of flooding: None  
Frequency of ponding: None  
Calcium carbonate maximum: 40 percent  
Gypsum maximum: 0 percent  
Available water capacity: Very low (about 2.1 inches)

##### Interpretive Groups

Land capability (non irrigated): 7s  
Ecological site: Gravel Breaks (R069XY064CO)

##### Typical Profile

0 to 6 inches: very gravelly sandy loam  
6 to 21 inches: extremely cobbly sandy loam, very cobbly sandy loam  
21 to 60 inches: extremely cobbly sand, very cobbly sand, extremely cobbly loamy sand

#### Midway

Percent of map unit: percent

## Map Unit Description

Fremont County Area, Colorado

### Shingle

Percent of map unit: percent