

# WELL LOCATION CERTIFICATE

NW CRN SEC. 2  
2.5" AC LS 23513

SECTION 2, TOWNSHIP 6 NORTH, RANGE 66 WEST, 6TH P.M.

NE CRN SEC. 2  
3.25" AC LS 38065

N88°51'40"E 2658.7' N88°51'42"E 2658.5'

N1/4 CRN SEC. 2  
3.25" AC LS 30462

N05°14'35"W 1242.7'  
1274.6'  
N05°14'39"W

BH = 1246' FNL,  
1304' FWL

2541.8'

1269.8'  
S05°33'43"E

W1/4 CRN SEC. 2  
3.25" AC LS 22098

N89°21'55"E

2672.5'

E1/4 CRN SEC. 2  
3.25" AC LS 22098

2634.7'

## NOTES:

THIS IS A DIRECTIONAL DRILL WELL.  
BOTTOM HOLE AT 1246' FNL, 1304' FWL.  
WELL FALLS IN A CORN FIELD.  
SEE LOCATION DRAWING FOR IMPROVEMENTS

GROUND ELEVATION = 4875'  
LAT. & LONG. = N 40.51762°  
W 104.74907°

S1/4 CRN SEC. 2  
3.25" AC LS 22098

SW CRN SEC. 2  
3.25" AC LS 28258

S89°30'00"W

2685.5'

S89°39'27"W

2670.9'

SE CRN SEC. 2  
2.5" AC LS 23501


BASIS OF BEARINGS

I HEREBY STATE TO PERTOLEUM DEV. CORP. THAT THIS WELL LOCATION CERTIFICATE  
FOR THE WELL ANDERSON 2AD IS LOCATED 2424' FNL & 1639' FWL, SEC. 2, T6N, R66W, 6PM.



## LEGEND

- = FOUND MONUMENT
- = PROPOSED WELL
- = BOTTOM HOLE



SCALE 1" = 1000'

ELEVATION SOURCE = USGS 7.5' QUAD.MAP CONTOURS  
NGVD 1929 DATUM.

LAT. & LONG. ARE DIFFERENTIALLY CORRECTED (NAD'83)  
USING (DGPS) WITH (PDOP) VALUES LESS THAN SIX (6).

SHOWN DISTANCES ARE FIELD MEASURED - EXTERIOR SECTION LINES  
ARE DRAWN TO SCALE (BEST APPROX. OR FOUND MONUMENT ).

THOMAS G. CARLSON, PLS 24657  
HORSESHOE SURVEYING, LLC

THIS IS NOT A MONUMENTED BOUNDARY SURVEY, IT IS ONLY A  
DRAWING INTENDED TO DEPICT THE WELL LOCATION TO SECTION LINES.

DISTANCES TO WELL SHOWN PERPENDICULAR  
TO SECTION LINES.

PREPARED BY:

HORSESHOE SURVEYING, LLC  
PO BOX 150458  
LAKEWOOD, CO 80215  
(720)872-0196

WELL NAME:

ANDERSON 2AD

LOCATION:

WELD COUNTY, CO  
NW1/4, SEC. 2, T6N, R66W, 6TH P.M.

DRAWING DATE:

8-10-10

FIELD DATE:

8-9-10

BY:

TGC

CHKD:

JOB NO.

SHEET NO.

1 OF 1