




PETROLEUM DEVELOPMENT CORPORATION

State Contact: David Andrews david.andrews@state.co.us

WELL NAME PUCKETT 11D-24D
API# 05-045-16104
LEASE#
PERMIT #

DATE 08/27/2010



CASING AND HOLE INFORMATION

DEPTH HOLE 2547
CASING 9 5/8 36#, 8rD, ST&C
DEPTH SET 2521.6

Cement report

Company : BJ

CASING STRING:

LEAD: 35:65 POZ plus additives 1435 sacks 12.5 ppg 1.95 yld 490bbl slurry mixed @ 5.2 bbl/min

TAIL: TYPE III plus additives 170 sacks 14.2 ppg 1.47 yld 48 bbl slurry mixed @ 3.4 bbl/min

DISPLACED Displaced w/191 bbls water @6 Dwn To 2.5 bbl/min bumped plug w/ 1274 psi Floats held. No returns to surface

PRESSURE BEFORE BUMPING PLUG: 300, plug bumped at 1274 psi

RETURN: 0% returns

COMENTS: Tested lines to 2960 psi

TOP OFF INFORMATION:

1	200 SKS, TYPE III, .04 lbs/sks static free, 10% A-10, 2% CaCl2
2	200 SKS TYPE III. .04 lbs/sks static free, 10% a-10, 2% CaCl2
3	175 SKS TYPE III. .04 lbs/SKS static free, 10% A-10, 2% CaCl2

CEMENT TO SURFACE AFTER THREE TOP OUTS.

Any Questions or problems please advise

Miles Pierson
801 - 520 - 3534