

FORM
5
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400089887

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: Kenny Trueax
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6383
3. Address: P O BOX 173779 Fax: (720) 929-7383
City: DENVER State: CO Zip: 80217-37

5. API Number 05-123-31366-00 6. County: WELD
7. Well Name: KERR-MCGEE Well Number: 15-3
8. Location: QtrQtr: NWSW Section: 3 Township: 1N Range: 68W Meridian: 6
Footage at surface: Direction: FSL Distance: 1659 Direction: FWL Distance: 1155
As Drilled Latitude: _____ As Drilled Longitude: _____
GPS Data:
Data of Measurement: _____ PDOP Reading: _____ GPS Instrument Operator's Name: _____
** If directional footage
at Top of Prod. Zone Distance: 515 Direction: FSL Distance: 3203 Direction: FWL
at Bottom Hole Distance: 510 Direction: FSL Distance: 3196 Direction: FWL
9. Field Name: WATTENBERG 10. Field Number: 90750
11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 08/08/2010 13. Date TD: 08/12/2010 14. Date Casing Set or D&A: 08/13/2010

15. Well Classification:
☐ Dry ☐ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8887 TVD 8394 17 Plug Back Total Depth MD 6256 TVD 5763

18. Elevations GR 4934 KB 4949 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
Preliminary Form 5

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Weight Per Foot	Setting Depth	Sacks Cement	Cement Bottom	Cement Top
SURF	12+1/4	8+5/8	24#	990	620	990	0
1ST	7+7/8	4+1/2	11.6#	8,867	1,005	8,867	989

REMEDIAL CEMENT

Cement work date: 08/13/2010

Details of work:

DV tool set at 6036'. Cement 2 stage job w/215 sacks 1st stage and 790 sacks 2nd stage, 1005 sacks total.

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	6,036	790	989	6,036

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,486		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,602		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	5,954		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,876		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	8,244		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,266		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,718		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Kenny Trueax

Title: Regulatory Analyst II

Date: _____

Email: kenny.trueax@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name	Doc Description
400089910	DIRECTIONAL SURVEY	KERR MCGEE Kerr McGee 15-3 Final Plot & Survey (08.18.10).pdf
400089921	CMT SUMMARY	Kerr McGee 15-3 Sfc Cement Tkt.pdf

Total Attach: 2 Files